

State of Kansas



15.185.19512.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 2 - 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Jim Lahar of B & B Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Robinowitz Oil Company

Complete Address: 1322 East 50th St., Tulsa, Oklahoma

Lease Name: Tammen Well No. # 1

Location: SW NE NE Sec. 6 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 1605' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole X

Mr. Lahar was instructed to plug the well as follows:

205' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sacks of hulls, and cement with 25 sacks. Fill hole, with drilling mud to 40' 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to the base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Cliving  
Conservation Division Agent