

State of Kansas



15.185.20058.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed September 15, 1967.

Dear Sir:

Mr. Duke Burt of Burt Drilling Company has this
date requested permission to plug the following described well:

Mr. Burt guarantees payment of the plugging fee.

Operator's full Name: L. K. Parrish

Complete Address: 714 Fourth National Bank Bldg., Wichita, Ks. 67202

Lease Name: Wanda Carey Well No. # 2

Location: NW SE SW Sec. 6 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3555' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burt was instructed to plug the well as follows:

310' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fill
hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent