

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1972
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Rice of Sterling Drilling Company has this
date requested permission to plug the following described well:Mr. Rice guarantees payment of the plugging fee.Operator's full Name: The Cherokee & Pittsburg Coal and Mining Company.Complete Address: 900 Polk Street, Amarillo, Texas.Lease Name: Harm Schneider Well No. 1Location: 1980' FNL & 1980' FEL Sec. 21 Twp. 15 Rge. (E)(W) 23County: Trego Total Depth 4621' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Rice was instructed to plug the well as follows:372'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 625'.Circulate hole with heavy mud. Pull DP to 900' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 400' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent