

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Blitting Building  
Wichita, Kansas

Stafford County. Sec. 28 Twp. 21 Rge. 12 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SW SE

Lease Owner M. Dizdar Petroleum Investment Co.

Lease Name Sittner Well No. 1

Office Address 1201 Main St., Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Aug. 18, 19 51

Application for plugging filed Aug. 18, 19 51

Application for plugging approved Aug. 18, 19 51

Plugging commenced Aug. 18, 19 51

Plugging completed Aug. 18, 19 51

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Charlie Stow

Producing formation Depth to top Bottom Total Depth of Well 3639 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	271'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cementer's plug pushed to 270'  
Cemented with 15 sacks of cement  
second plug set at 40' and cemented  
with 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Dizdar & Nye Drilling Company  
Address Drawer 30, Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.  
Glenn R. Nye (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glenn R. Nye  
Drawer 30, Hays, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of August 19 51

My commission expires May 9, 1953

Robert L. Spiess  
STATE CORPORATION COMMISSION  
Notary Public.

PLUGGING  
FILE SEC 28 T 21 R 18  
BOOK PAGE 124 LINE 26

SEP 4 X 1951  
CONSERVATION DIVISION  
Wichita, Kansas

Company: M. Dizdar Petroleum Investment Company  
Contractor: Dizdar & Nye Drilling Company  
Commenced: August 5, 1951  
Completed: August 18, 1951

Farm: Sittner No. 1  
SE SW SE Sec. 28-21S-12W  
Stafford County, Kansas  
Casing Record: 8 5/8" casing set at 271'

( Figures below indicate bottoms)

sand	225		
red bed & sand	272		
red bed	485		
red bed, sand & shale	650		
anhydrite	670		
shale & sand	965		
shale & lime	1265		
shale	1525		
lime & shale	1650		
shale & lime	1745		
lime & shale	1875		
lime & shale	1965		
lime & shale	2030		
shale & lime	2130		
shale & lime	2270		
lime & shale	2405		
shale & lime	2530		
shale & lime	2630		
shale & lime	2710		
shale & lime	2815		
shale & lime	2877		
lime & shale	2920		
lime & shale	3005		
shale & lime	3070		
lime & shale	3125		
shale & lime	3200		
lime & shale	3275		
lime	3330		
lime & shale	3380		
lime & shale	3400		
lime	3415		
lime & shale	3440		
lime & shale	3480		
lime	3525		
lime & shale	3565		
shale & lime	3600	Simpson sand	3614'
shale & lime	3619	Arbuckle	3616'
lime	3621		
lime	3630		
lime	3639	T.D.	

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

DIZDAR & NYE DRILLING COMPANY

By Glenn R. Nye

STATE OF KANSAS }  
ELLIS COUNTY } SS

Subscribed to and sworn to before me, a notary public, in and for said County and State this 31st day of Aug., 1951.

My Commission Expires May 9, 1953

PLUGGING  
FILE SEC 28-21-12W  
BOOK PAGE 64 LINE 26

John L. Spiess  
Notary Public  
RECEIVED  
STATE CORPORATIONS COMMISSION  
SEP 4 X 1951  
COMMERCIAL DIVISION  
Wichita, Kansas