

15.185.21819.0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Stafford SEC. 28 TWP. 21 RGE. 12 E/W  
 Location as in quarters or footage from lines:  
SW/SW/SE


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Petroleum, Inc.  
 Lease Name Sittner "D" Well No. #5  
 Office Address P. O. Box 1447 - Great Bend, Ks. 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced August 11, 1983  
 Plugging completed August 15, 1983  
 Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3620'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	264'	NONE
				5 1/2"	3619'	2796.97'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Dumped sand to 3570' and five (5) sacks cement.  
Shot pipe @ 2800'.  
Pulled sixty-eight (68) joints 5 1/2" casing.  
Squeezed well with four (4) sacks hulls, fifteen (15) sacks gel,  
fifty (50) sacks cement, ten (10) sacks gel, released plug, and  
pumped one hundred (100) sacks 60/40 pozmix cement with 2% added  
gel and 3% calcium chloride.

116 22 1983  
 8-22-83  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.  
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1983



Margaret Prosser  
 Notary Public.

My Commission expires: \_\_\_\_\_

15.185.21819.0000

K. T. WOODMAN  
RES. PHONE 733-0418  
OFF. PHONE 265-7650  
WICHITA, KANSAS

D. J. IANNITTI  
PHONE 792-2921  
GREAT BEND, KANSAS

# WOODMAN & IANNITTI DRILLING COMPANY

*Rotary Drilling Contractors*

1022 UNION CENTER  
150 N. MAIN  
WICHITA, KANSAS 67202

July 22, 1983

Company:	Petroleum, Inc.
Farm:	Sittner "D" #5
Location:	SW SW SE
Section:	28-21S-12W
County:	Stafford
Contractor:	Woodman & Iannitti Drilling Company
Total Depth:	3620'
Comm:	July 11, 1983
Comp:	July 19, 1983
Casing:	8-5/8" set @ 264' w/225 sx. Common 5 1/2" set @ 3619' w/100 sx. 50/50 Pozmix

Figures Indicate Bottom Formations:

15	Sandy Clay
225	Sand
264	Shale
648	Shale & Red Bed
671	Anhydrite
1025	Shale
1289	Shale
1580	Shale & Lime
1818	Shale
2065	Lime & Shale
2338	Lime & Shale
2608	Shale & Lime
2803	Lime & Shale
2907	Lime & Shale
3088	Lime & Shale
3233	Lime & Shale
3325	Lime & Shale
3375	Lime
3394	Lime
3420	Lime
3451	Lime
3522	Lime
3620	Lime

RECEIVED  
STATE CORPORATION COM.

AUG 12 1983

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

*K. T. Woodman*  
K.T. Woodman, Partner