


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 28 Twp. 21S Rge. 12 (X) (W)  
Location as "NE/CNW/SW" or footage from lines G-NE-NE-NE  
Lease Owner Sunray Oil Corporation  
Lease Name Ziegenbusch Well No. 1  
Office Address Box 195, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed January 1, 19 53  
Application for plugging filed January 15, 19 53  
Application for plugging approved January 16, 19 53  
Plugging commenced February 6, 19 53  
Plugging completed February 12, 19 53  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3660 Feet  
Show depth and thickness of all water, oil and gas formations. PB 3401

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Iansing</u>	<u>Dry</u>	<u>3262</u>	<u>3485</u>			
<u>Arbuckle</u>	<u>Dry</u>	<u>3570</u>	<u>3660</u>	<u>8 5/8</u>	<u>324</u>	<u>none</u>
				<u>5 1/2</u>	<u>3571</u>	<u>2750</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded hole from 3410' to 3370' and ran 5 sax of cement. Bailed hole to 324', mudded hole to 300', set 10' rock bridge and ran 20 sax of cement. Mudded hole 45', set 15' rock bridge and ran 10 sax of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
W. E. Westbrook, Jr. (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr.  
Box 195, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of February, 19 53

My commission expires December 24, 1956

24-2675-5 2-32-20M

**PLUGGING**  
FILE SEC 28 T 21 R 12  
BOOK PAGE 78 LINE 10

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 23 1953  
CONSERVATION DIVISION  
Wichita, Kansas  
2-23-1953

Notary Public.

H. H. Ziegenbusch No. 1 Well  
Sec. 28-21S-12W, Stafford County, Kansas

Drilled for: Sunray Oil Corporation  
Drilled by: Mouser Drilling Company

Drilling Commenced: November 30, 1952  
Drilling Completed: December 13, 1952

Casing Record:

8 5/8" 324' 24# 8rd Thd Casing  
5 1/2" 3571' 17# 8rd Thd Casing

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
Sand	175
Shale	260
Red Bed	580
Red Rock	645
Anhydrite	675
Shale & Shells	1150
Salt	1425
Shale & Lime	1575
Lime	1685
Shale & Lime	1800
Sand & Lime	1845
Lime	2030
Lime & Shale	2275
Shale & Lime	2400
Shale & Shells	2580
Lime & Shale	2665
Shale & Lime	2800
Lime	2935
Sandy Lime	3005
Lime	3165
Lime & Shale	3250
Lime	3497
Viola	3520
Shale	3570
Arb Lime	3573
Total Depth	3573'

FORMATION DEPTH

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the above described location to the best of my knowledge and belief.

Wm. Mouser

Subscribed and sworn to before me this 14th day of December 1952.

**PLUGGING**  
FILE SEC 28-21-12W  
BOOK PAGE 78 LINE 10

Frances L. Webber  
Notary Public

STATE OF KANSAS, COUNTY OF SEDGWICK

FEB 23 1953

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:  
March 18 1954