

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 32 TWP. 21S RGE. 12W E/W
Location as in quarters or footage from lines:
C N/2 N/2 SW/4

Lease Owner Energy Reserve Group, Inc.
Lease Name Leona Walker #2 Well No. _____
Office Address 925 Patton Road Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 2-19-82
Plugging completed 2-23-82
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz
Producing formation _____ Depth to top _____ bottom T.D. 3636'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	687'	none
				5-1/2"	3630'	2280'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 3250' and ran 5 sacks cement. Shot casing @2418' and
2295', pulled a total of 56 joints of pipe. Plugged well with 5 sacks hulls, 25 sacks
gel, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1982

(Signature) R. Darrell Kelso
Box 176 Chase, Kansas 67524
(Address)

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 25th day of February, 1982



My Commission expires:

Irene Hoover
Notary Public.

DRILLERS LOG

OPERATOR: Energy Reserves Group, Inc.
925 Patton Road
Great Bend, Kansas 67530

WELL NAME: #2 Walker
N/2 N/2 SW Sec.32-21S-12W
Stafford County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 5/21/81

COMPLETED: 5/30/81

RTD: 3636'

SURFACE CASING: 8-5/8" set at 687' with 450 sx

PRODUCTION CASING: 5-1/2" set at 3634' with 200 sx

0' to 672' Sand & Shale
672' to 970' Anhydrite & Shale
970' to 1460' Sand & Shale
1460' to 3195' Lime & Shale
3195' to 3342' Shale & Lime
3342' to 3366' Lime
3366' to 3478' Lime & Shale
3478' to 3636' Lime (Arbuckle)
RTD 3636'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Co., Inc.
hereby state the above is an accurate copy of the Walker #2 log for
Energy Reserves Group, Inc.

James C. Remsberg
James C. Remsberg

Subscribed and sworn to me
this 11th day of June, 1981

Mary Lou Taylor
Mary Lou Taylor, Notary

My commission expires January 17, 1985

RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1982
CONSERVATION DIVISION
Wichita, Kansas

