


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 32 Twp. 21S Rge. (X) 12 (W)

Location as "NE/CNW/SW" or footage from lines NE NW SE  
Lease Owner John C. Graves & Meltzer Oil Company  
Lease Name Walker Well No. 3  
Office Address 412 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 6, 19 64  
Application for plugging filed March 6, 19 64  
Application for plugging approved March 6, 19 64  
Plugging commenced March 6, 19 64  
Plugging completed March 6, 19 64  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3628 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 260 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/4 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 12 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Graves Drilling Co., Inc.  
Address 412 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF BUTLER, ss.  
John C. Graves (employee of owner) or (matters or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
412 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of March, 19 64

My commission expires April 30, 1967 Betty Brandt Notary Public.

R O T A R Y D R I L L E R S ' L O G

OPERATOR: John C. Graves and Meltzer Oil Company  
412 Union Center  
Wichita, Kansas  
DRILLING COMMENCED: February 27, 1964

CONTRACTOR: Graves Drilling Co., Inc.  
412 Union Center  
Wichita, Kansas  
DRILLING COMPLETED: March 6, 1964

CASING RECORD: 8 Jts. 271' of 8-5/8" surface casing cemented with 300 sacks cement  
LOCATION: Walker No. 3  
NE NW SE  
Section 32-21S-12W  
Stafford County, Kansas

-----			
0 - 220	Sand	3070 - 3135	Shale
220 - 271	Red bed	3135 - 3250	Shale & lime
271 - 820	Red rock & shale	3250 - 3269	Shale
820 - 1093	Shale	3269 - 3506	Lime
1039 - 1470	Shale & shells	3506 - 3519	Shale
1470 - 1965	Shale & lime	3519 - 3562	Lime
1965 - 2183	Lime & shale	3562 - 3565	Sandy shale
2183 - 2547	Shale	3565 - 3621	Sand
2547 - 2755	Lime & shale	3621 - 3623	Shale
2755 - 2930	Shale & lime	3623 - 3628	Lime
2930 - 3070	Shale	3628	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves  
President

RECEIVED  
STATE CORPORATION COMMISSION

MAR 12 1964

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
BUTLER COUNTY ) ss

Subscribed and sworn to before me, a Notary Public, this 11th day of March, 1964.

My commission expires:

April 30, 1967

Betty Bradt  
Betty Bradt Notary Public