

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biltmore Building
Wichita, Kansas

Stafford County, Sec. 32 Twp. 21 Rge. 12 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines W $\frac{1}{2}$ SE NW

Lease Owner Dizdar Petroleum Investment Company

Lease Name Mueller Well No. I

Office Address 1201 Main Street, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 19 19 51

Application for plugging filed February 2 19 52

Application for plugging approved February 2 19 52

Plugging commenced February 2 19 52

Plugging completed February 25 19 52

Reason for abandonment of well or producing formation failed to produce - dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Arbuckle Depth to top 3615 Bottom 3621 Total Depth of Well 3621 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	264'	
				4 1/2"	3615'	APPOX. 104 jts. pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated with cement, run 4 1/2" - 3615'. Put 125 sacks cement back of it. Top perforation in 4 1/2" - 3450'. Plugged back with Lane Wells Plug below perforation. Filled hole with sand to 3440'. Dumped 3 sacks cement. Shot pipe off and pulled approximately 104 jts. Mudded hole up to bottom of 8 5/8" - 264'. Set a Rock Bridge and 15 sacks cement. Filled hole with mud to within 35' of base of sub. Set Rock Bridge and 10 sacks cement.

3-15-52

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Dizdar Petroleum Investment Company
Address 1201 Main Street
Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Marko Dizdar (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Marko Dizdar
1201 Main Street, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of March, 19 52

Eleanor Tobias
Notary Public.

My commission expires February 6, 1956

23-5091-s 8-50-10M

PLUGGING
FILE SEC 5 Y 21R 122
PAGE 126 LINE 43

Company: M. Dizdar Petroleum Investment Company
 Contractor: Dizdar & Nye Drilling Company
 Commenced: August 19, 1951
 Completed: September 6, 1951

Farm: Mueller No. 1
 Location: CW $\frac{1}{2}$ SE NW Sec. 32-21S-12W
 Stafford County, Kansas
 Casing Record: 8 5/8" set at 264'
 4 1/2" set at 3617'

(Figures below indicate bottoms)

clay	20
sand	125
shale & shells	264
red bed	450
red bed	675
anhydrite	705
shale & sand	725
shale	1170
shale, sand & salt	1440
shells, shale & lime	1570
shale & lime	1680
lime & shale	1815
shale & lime	1950
shale & lime	2045
shale & lime	2160
shale & lime	2285
lime & shale	2435
shale & shells	2610
lime & shale	2730
shale & lime	2840
lime & shale	2930
shale & lime	3025
shale & lime	3090
lime & shale	3140
shale & lime	3200
shale & lime	3260
lime	3319
lime & shale	3370
lime & shale	3415
lime	3442
lime & shale	3490
lime & cherty	3540
lime & chert	3565
lime & shale	3615
lime & shale	3621

Arbuckle 3616'
 T. D. 1873'
 1743'

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

DIZDAR & NYE DRILLING COMPANY

STATE OF KANSAS)
) SS
 ELLIS COUNTY)

BY Glenn B. Nye

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 16th day of Sept, 1951.

John L. Spivey
 Notary Public

My Commission Expires: May 9, 1953