STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

15-009-22454-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 29 TWP. 16 RGE. 12 E/W
Location as in quarters or footage from lines:
NE NW NW



Locate Well correctly on above Section Platt.

Lease Owner Reif Oil Operations
Lease Name Hitschman "C" Well No. #1
Office Address Box 298 Hoisington, Kansas 67544
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 8-21-81
Application for plugging filed 8-21-81
Plugging commenced 8-21-81 1:10 PM
Plugging completed 8-21-81 5:15 PM
Reason for abandonment of well or producing formation
Dry Hole
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top bottom T.D. 3450'
Show depth and thickness of all water, oil and gas formations.
331' of 8 5/8

OIL, GAS OR WATER RECORDS — Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to600' with heavy mud and mixed 60 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 300' with heavy mud and mixed 40 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 40 ' built bridge pushed down plug and mixed 10 sacks and filled hole to the bottom of cellar; mixed 5 sacks and poured into the rat hole.

All cement used was 50-50 Poz Mix 6% Gel 3% CC

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Future Drlg., Inc.

STATE OF Kansas COUNTY OF Russell ,ss.
Stanley C. Lingreen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stanley C Lingreen
Box 293 Russell, Kansas 67665
(Address)

PAULA J. GIBSON
State of Kansas
My Appt. Exp. 11-10-84

SUBSCRIBED AND SWORN TO before me this 24th day of August, 1981

Paula J. Gibson
Notary Public.

My Commission expires: November 10, 1984

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1981

DRILLERS' WELL LOG

DATE COMMENCED: August 22, 1981
DATE COMPLETED: August 30, 1981

Raymond Oil Co. Inc.
DELLENBACH #1
SE/4 SW/4 SE/4
Sec. 18-T24S-R7W
Reno County, Ks.

0 - 3518' Surface Soil, Shale, Lime
3518' RTD

ELEVATION: 1629 K.B.

FORMATION DATA

No tops available from geologist.
RTD 3518'

SURFACE PIPE: Set new 20# 8-5/8" pipe at 358' w/225 sacks common, 2% gel, 3%cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Darrel Anderson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Darrel Anderson

Subscribed and sworn to before me this 31 day of August, 1981.

Dorothy M Hague
Notary Public

My Comm. Expires: April 11, 1982

RECEIVED
STATE CORPORATION COMMISSION
SEP - 3 1981
CONSERVATION DIVISION
Wichita, Kansas

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

S. 29 T. 16 R. 12 E W

API No. 15 — ____ — ____
County Number

Loc. NE NW NW

County Barton

640 Acres



Locate well correctly

Operator: Reif Oil Operations

Address: Box 298 Hoisington, Kansas 67544

Well No.	Lease Name
#1	Hitschman "C"

Footage Location: ____ feet from (N) (S) line ____ feet from (E) (W) line

Principal Contractor	Geologist
Future Drlg., Inc.	Jim Musgrove

Spud Date	Date Completed	Total Depth	P.B.T.D.
8-15-81			

Directional Deviation: ____ Oil and/or Gas Purchaser: ____

Elev.: Gr. ____

DF ____ KB 1926'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	20#	331'	50-50 Poz Mix	190	3% CC
Production	Dry Hole						

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

TUBING RECORD

Size	Setting depth	Packer set at

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1981
CONSERVATION DIVISION
Wichita, Kansas

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold): ____ Producing interval(s): ____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

C-10-1972

Operator	DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Reif Oil Operations	

Well No.	Lease Name	
#1	Hitschman "C"	Dry Hole

S 29 T 16 R 12 E/W NE NW NW

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale	000	260		
Sand	260	334		
Shale & Clay	334	850		
Anhydrite	850	877		
Shale & Red Bed	877	1125		
Shells & Shale	1125	1855		
Lime & Shale	1855	3450	R.T.D.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Paula J. Gibson
Signature

Bookkeeper Future Drlg., Inc.
Title

August 24, 1981
Date