

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton

County. Sec. 29 Twp. 16S Rge. 12 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE/4 SE/4 NE/4

Lease Owner Derby Drilling Company

Lease Name Laudick "B" Well No. 1

Office Address 352 North Broadway, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil 1

Date well completed February 6 19 52

Application for plugging filed July 25 19 56

Application for plugging approved July 26 19 "

Plugging commenced July 27 19 "

Plugging completed August 1 19 "

Reason for abandonment of well or producing formation No Longer Commercially Productive

If a producing well is abandoned, date of last production July 19 56

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R/ M. Brundege

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3367 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	190	-0-
				5-1/2	3367	2551

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with sand from 3374 to 3115 - dumped 5 sacks cement; circulated hole with heavy mud; spotted 75 sacks cement @ 330' with pump truck; mudded to 35'; dumped cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 18 1956

08-18-56

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & D Casing Pulling Company (License #236)  
Address Box 569, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

L. H. Myrick (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

L. H. Myrick  
(L. H. Myrick)

352 North Broadway, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of August, 19 56

My commission expires 10/28/1959

Notary Public.

PLUGGING  
FILE SEC. 29 T. 16 R. 12 W  
BOOK PAGE 83 LINE 44

**ROCKET DRILLING COMPANY**  
**352 NORTH BROADWAY**  
**WICHITA 2, KANSAS**

DERBY DRILLING COMPANY, ETAL  
 352 NORTH BROADWAY  
 WICHITA 2, KANSAS

#1 LAUDICK "8"  
 SE SE NE; 29-16-12W  
 BARTON COUNTY, KANSAS

ELEVATION: 1903 Gr., 1906 D.F., 1908 R.B.  
 SPUDDED: JANUARY 20, 1952  
 ROTARY COMPLETED: JANUARY 29, 1952  
 CABLE TOOLS COMPLETED:  
 ACID TREATMENT:  
 CONTRACTOR: ROCKET DRILLING COMPANY

CASING RECORD

190' 8-5/8" O. D. 2 1/4# SEAMLESS CASING CEMENTED W/135 SACKS CEMENT.  
 3367' 5-1/2" O. D. 1 1/4# SEAMLESS CASING CEMENTED W/125 SACKS CEMENT.

DRILLERS LOG

SHALE & SHELLS	0 TO 190	LIME	1925 TO 2210
SHALE, SHELLS & SAND	816	LIME & SHALE	2555
ANHYDRITE	845	LIME	2615
SHALE & SHELLS	1320	SHALE & LIME	2789
SHALE & SALT	1340	LIME	2885
SALT & SHALE	1628	LIME & SHALE	2945
LIME & SHALE	1820	LIME	2993
LIME	1870	LIME & SHALE	3070
SAND	1890	SHALE & LIME	3122
SHALE & LIME	1925	LIME	3368 TD

STATE OF KANSAS)  
 SEDGWICK COUNTY) SS:

I HEREBY CERTIFY THAT TO THE BEST OF MY KNOWLEDGE AND BELIEF,  
 THE FOREGOING LOG IS TRUE AND CORRECT.

ROCKET DRILLING COMPANY

BY \_\_\_\_\_

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC, IN AND FOR  
 THE STATE AND COUNTY AFORESAID THIS 31ST DAY OF JANUARY, 1952.

My COMMISSION EXPIRES: 12-3-55

\_\_\_\_\_  
 NOTARY PUBLIC

**PLUGGING**

FILE SEC. 29, T. 16, R. 12W

BOOK PAGE 83 LINE 44