

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

REC'D JAN 4 1956

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 24 Twp. 21S Rge. 13 (E) (W)

T 21S NORTH R 13W

			*
	24		

Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines SW NE NE  
 Lease Owner Pam-Kar Drilling Company  
 Lease Name Schmalian Well No. 1  
 Office Address 333 First Nat'l. Bank - Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Oil well  
 Date well completed January 11 19 54  
 Application for plugging filed December 13 19 55  
 Application for plugging approved December 14 19 55  
 Plugging commenced December 27 19 55  
 Plugging completed December 30 19 55  
 Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Brundege  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3595 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	270'	None
				5-1/2"	3588'	2957'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with sand from 3595' to 3580' and ran 5 sacks of cement. Mudded the hole to 260', set a 10' rock bridge and ran 20 sacks of cement at 250'. Mudded the hole to 40', set a 10' rock bridge and ran 10 sacks of cement to fill to base of cellar. Plugging completed.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 7 1956  
CONSERVATION DIVISION  
WICHITA, KANSAS  
1-9-1956

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor West Supply Co., Inc.  
 Address Chase, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
I, Ralph B. McLaughlin (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B. McLaughlin

SUBSCRIBED AND SWORN to before me this 6th day of January, 19 56

(Address) \_\_\_\_\_  
Donna L. Riley  
 Donna L. Riley Notary Public.

My commission expires December 31, 1958

PLUGGING  
 P.M. SEC 24 T. 21S R. 13W  
 BOOK PAGE 23 LINE 38

PAM-KAR DRILLING CO., INC.  
WICHITA, KANSAS

Well: Schmalian # 1

SW NE NE  
24-21S-13W  
Stafford County  
Elevation 1869-1867

COMMENCED R.D. 1/1/54  
COMPLETED R.D. 1/11/54  
TOTAL DEPTH 3595'

Contractor: Pam-Kar Drllg.

Casing: 270' 8 5/8" 8 rnd thd 24# - 275' Lot  
3588' 5 1/2" OD 14# 8rnd thd 75' Lot

STRATA	DEPTH	TOPS
Sand	5	Heebner 3146-1275
Surface Soil & Clay	10	Brown Lime 3273-1402
Sand & Shale	204	Lansing 3290-1419
Shale	274	Cong. 3528-1657
Red Beds	740	Arbuckle 3586-1715
Anhydrite	1010	
Shale	1140	
Shale & Shells	1265	
Salt & Shale	1335	
Shale & Shells	1545	
Lime & Shale	1627	
Broken Lime	1912	
Lime & Shale	1980	
Broken Lime	2086	
Lime & Shale	2370	
Shale & Lime	3032	
Lime & Shale	3142	
Shale & Lime	3225	
Lime & Shale	3543	
Lime, sand & Chert	3569	
Lime & Shale	3595	
Total Depth	3595	

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

PAM-KAR DRILLING COMPANY, INC.  
BY

*Ralph B. McLaughlin*  
R.B. McLaughlin, Sec. & Treas.

Signed and sworn to in my presence this 25th day of January, 1954, by Ralph B. McLaughlin, Secretary of the Pam-Kar Drilling Company, Inc. a corporation in the State of Kansas.

*John Taylor*  
Notary Public

My commission expires Sept. 4, 1957.

**PLUGGING**  
FILE SEC 24 T 21 R 13 W  
BOOK PAGE 23 LINE 38

RECEIVED  
STATE CORPORATION DIVISION  
DEC 14 1955  
CONSERVATION DIVISION  
Wichita, Kansas