

R

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stafford County, Sec. 23 Twp. 21S Rge. 13 (E) (W)X  
Location as "NE/CNWSW" or footage from lines NW SW NW

Lease Owner Circle Oil Company, Inc.  
Lease Name Schmalian Well No. 1  
Office Address 500 Bitting Building Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 4-19-67 19  
Application for plugging approved 19  
Plugging commenced 5-18-67 19  
Plugging completed 5-23-67 19  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation Depth to top Bottom Total Depth of Well 3692 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	265	None
				5 1/2	None	2591

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 29 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaning out cellar.

Sanded to 3100'. Dumped 5 sacks of cement. Working pipe. Shot pipe at 2750' - 2643' and 2550'.

Working pipe. Pulling pipe.

Pulling pipe. Pushed plug to 260' rock bridge. Dumped 12 sacks of cement.

Bailed hole dry. Dumped 13 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of May 19 67

Notary Public

My commission expires May 27, 1969

DRILLERS LOGSCHMALIAN NO. 1

CASING RECORD:	COMPANY:	Circle Oil Co., Inc.	DESCRIPTION:
8-5/8" @ 265' w/225 sax cement	CONTRACTOR:	Sage Drilling Co.	NW SW NW Sec. 23-21S-13W Stafford Co., Kansas
TOTAL DEPTH: 3692'	COMMENCED:	August 3, 1966	ELEVATION: 1874KB
	COMPLETED:	August 13, 1966	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	267	<p style="text-align: center;"><b>RECEIVED</b> STATE CORPORATION COMMISSION</p> <p style="text-align: center;">MAY 1 1967</p> <p style="text-align: center;">CONSERVATION DIVISION Wichita, Kansas</p>
Shale & Sand	267	724	
Anhydrite	724	752	
Red Bed & Blue Shale	752	800	
Shale & Lime	800	2125	
Lime & Shale	2125	3586	
Cherty Lime & Shale	3586	3627	
Lime & Shale	3627	3692	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

BY Lawrence F. Gray  
Lawrence F. Gray

Subscribed and sworn to before me this 18th day of August, 1966.

Louise K. Whitted  
Louise K. Whitted - Notary Public

My commission expires:  
November 26, 1966.