

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185,22372.0000

LEASE NAME Schmalian

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line
SW SW NW

SEC. 23 TWP. 21 RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed 5-3-86

Plugging Commenced 12-21-87

Plugging Completed 12-30-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Blackhawk Energy Corporation

ADDRESS P.O. Box 1910
Great Bend, Kansas 67530

PHONE # (316) 792-8141 OPERATORS LICENSE NO. 4104

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. # 1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3686'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	303'	none
				5-1/2"	3685'	2451'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off botto with sand to 3250' and 5 sacks cement. Shot pipe @2885', 2704', 2611', 2451', pulled a total of 60 joints of 5-1/2" casing. Plugged surface with 4 hulls, 10 gal, 50 cement, 10 gal, 1 hull, plug and 100 cement, 60/40 pos, 6% gel. Plugging Complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss. JAN 04 1988
1-4-1988

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 87

Jane Hoover
Notary Public

My Commission Expires:



WAYNE DOBBS, INC.

TELEPHONE (316) 793-3282

P. O. BOX 315


GREAT BEND, KANSAS 67530

CASING RECORD

Globe Exploration, Inc.
Box 12
Great Bend, Kansas 67530

RE: Schmalian # 1
SW SW NW
Sec. 23 T21 R13
Stafford County, Ks.

DATE: May 3, 1986
TOTAL DEPTH: 3686'
DEPTH PIPE SET: 3684' (or 2' off bottom)
CASING: 91 joints new 14# 5½" casing tally 3685.10 thds. off
SHOE JOINT: 12.90'
CEMENT: 500 gallon Mud Flush + 10 bbls. Salt Flush + 150 sacks 60/40
Posmix with 10% Salt & 3/4 of 1% CFR2
CENTRALIZERS: Ran 4
ZERO POINT: 5' above ground level
PLUG DOWN: 10:45 a.m.



Wayne Dobbs

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1986

CONSERVATION DIVISION
Wichita, Kansas