


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

STAFFORD County. Sec. 31 Twp. 21S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE

Lease Owner JAMES M. STEWART

Lease Name WETIG Well No. 2

Office Address UNION CENTER BUILDING

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed AUGUST 3, 19 67

Application for plugging filed ~~(PHONE 8/3/67)~~ AUGUST 14, 19 67

Application for plugging approved (PHONE 8/3/67) AUGUST 3, 19 67

Plugging commenced AUGUST 3, 19 67

Plugging completed AUGUST 3, 19 67

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING

Producing formation Depth to top Bottom Total Depth of Well 3757 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	305'	8-5/8"	305'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PUMPED 20 BBLs. HEAVY MUD AHEAD OF CEMENT SQUEEZE w/80 SX. COMMON. JOB BY HALLIBURTON.
JOB COMPLETED AT 4:30 PM, 8/3/67.

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.

Address 830 SUTTON PLACE, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

E. E. HALL

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

830 SUTTON PLACE, WICHITA, KANSAS 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of AUGUST 19 67

Barbara J. Layton
BARBARA J. LAYTON Notary Public.



MY COMMISSION EXPIRES FEB. 1, 1968

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

WETIG #2
 SE SE NE SECTION 31-21S-13W
 STAFFORD COUNTY, KANSAS

COMMENCED: JULY 24, 1967
 COMPLETED: AUGUST 3, 1967

OPERATOR - JAMES M. STEWART

DEPTH		FORMATION	REMARKS
FROM	TO		
0	40	CLAY AND SAND	
40	50	CLAY	
50	150	SAND	
150	250	SHALE	
250	295	SAND	
295	305	SHALE	RAN 16 JOINTS 8-5/8" CASING, SET @ 305' w/400 SACKS CEMENT.
305	400	SHALE	
400	794	SHALE, SHELLS AND RED BED	
794	820	ANHYDRITE	
820	850	SHALE	
850	1236	SHALE AND LIME	
1236	1745	SHALE AND SHELLS	
1745	2525	SHALE AND LIME	
2525	2762	SHALE	
2762	2840	SHALE AND SHELLS	
2840	3400	SHALE AND LIME	
3400	3610	LIME	
3610	3670	LIME AND SHALE	
3670	3705	CHERT	
3705	3757	LIME	
3757	TD		DRY AND ABANDONED.

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 16 1967
 REGISTRATION DIVISION
 WICHITA, KANSAS

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE SE SE NE SECTION 31-21S-13W, STAFFORD COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 8TH DAY OF AUGUST, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton

 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.

