


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 31 Twp. 21 Rge. 13 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW/SE/NE
Lease Owner Wilkinson Drilling, Inc.
Lease Name Wetig Well No. #1
Office Address East 10th, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced 8-31 19 58
Plugging completed 9-8 19 58
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3811' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"		
				4 1/2"		3,003'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3811'.
Plugging started 8-31-58. Finished 9-8-58.
Plugged off bottom with sand to 3740'. Dumped 4 sacks cement.
Worked and shot pipe. Shot 4 1/2" casing at 3,003'. Circulated and spotted oil. Pulled 4 1/2" casing out of hole. Squeezed well with 15 sacks mud and 80 sacks cement. Well completed.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.C. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
(Address) Box 221, Great Bend, Kan

SUBSCRIBED AND SWORN TO before me this 9th day of September, 1958
Betty S. Edmunds Notary Public

My commission expires 9 months 8, 1960

PLUGGING
FILE SEC 31 T. 21 R. 13W
BOOK PAGE 129 LINE 39
9-19-1958

WETIG NO. 1

Company	- WILKINSON DRILLING, INC.	Location	- NW SE NE, 31-21s-13w, Stafford County, Kansas
Contractor	- Company Tools	Elevation	- 1916' KB
Commenced	- January 5, 1958	Casing	- 8 5/8" @ 300' w/185 sks Cmn Cem
Completed	- July 14, 1958		4 1/2" @ 3809' w/80 sks Cmn Cem
Total Depth	- 3811'		

FIGURES INDICATE BOTTOMS OF FORMATIONS

<u>Depth</u>	<u>Formation</u>
0 - 210	Sand and Shale Streaks
210 - 795	Shale and Red Beds
795 - 830	ANHYDRITE
830 - 1710	Shale and Shells
1710 - 2405	Lime and Shale
2405 - 2595	Shale and Lime
2595 - 3250	Lime and Shale
3250 - 3376	Shale and Lime Streaks
3376 - 3642	Lime with Shale Streaks
3642 - 3700	Chert
3700 - 3749	Shale
3749 - 3811	Dolomite

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1964

CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Wetig No. 1, located in the NW SE NE, 31-21s-13w, Stafford County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Verhulst

Subscribed and sworn to before me this twenty-ninth day of July, nineteen hundred and fifty-eight.

Carolyn F. Moore

My Commission expires January 2, 1961.