

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stafford County. Sec. 31 Twp. 21S Rge. 13 ~~(E)~~ X (W)

Location as "NE/CNW/SW" or footage from lines CS/2 NE/4 NE/4

Lease Owner J. M. Stewart

Lease Name Wetig Well No. 1

Office Address 608 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-15 19 66

Application for plugging filed by phone 11-15 19 66

Application for plugging approved by phone 11-15 19 66


Plugging commenced 11-15 19 66

Plugging completed 11 A.M. 11-15 19 66

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes, by phone



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3778 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	304.81	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 275 feet;  
set plug at 275 with 25 sacks cement  
through drill pipe. Filled hole with  
mud to 40 feet; set plug with 10 sacks  
cement; 2 sacks cement in rathole.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 18 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

Address 830 Sutton Place, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
James M. Stewart (employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Stewart

608 Union Center, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 17th day of November, 19 66

My commission expires November 14, 1968

Notary Public

15.185.30339.0000

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 18 1966  
CONSERVATION DIVISION  
Wichita, Kansas

Well #1  
S/2 NE NE Section 31-21S-13W  
Stafford County, Kansas

Commenced: November 6, 1966  
Completed: November 15, 1966

Operator - James M. Stewart

DEPTH		FORMATION	REMARKS
From	To		
0	230	Soil and sand	
230	302	Shale	Ran 12 joints of 8-5/8" casing set @ 302' w/225 sacks cement.
302	810	Red bed	
810	840	Anhydrite	
840	980	Shale	
980	1700	Shale and shells	
1700	1975	Lime and shale	
1975	2130	Lime	
2130	3080	Lime and shale	
3080	3175	Lime	
3175	3245	Lime and shale	
3245	3355	Sandy shale and lime	
3355	3395	Shale and lime	
3395	3445	Lime	
3445	3490	Lime and shale	
3490	3635	Lime	
3635	3685	Lime and shale	
3685	3778	Lime	
3778	TD		Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the S/2 NE NE Section 31-21S-13W, Stafford County, Kansas, to the best of my knowledge and belief.

E. E. HALL

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 16th day of November, 1966, personally appeared E. E. HALL, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day year last above written.

  
Barbara J. Layton, Notary Public

My Commission Expires February 1, 1968.