

ATE OF KANSAS
ATE CORPORATION COMMISSION
3 S. Market, Room 2078
Chita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-185-01855-00-00

LEASE NAME Dorfshaffer

WELL NUMBER 1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 5 TWP. 21S RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 12-10-01

Plugging Completed 12-11-01

RECEIVED

DEC 21 2001

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS P.O. Box 20380 Wichita, Kansas 67202

PHONE (316) 265-3311 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Is plugging proposal was approved on _____ (date)

By Richard Lacey (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3544

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 830' | None |
| | | | | 5-1/2" | 3543' | 2021' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 3200' and 5 sx. cement. Shot pipe @2021', pulled up to 860', pumped 10 sx. gel and 50 sx. cement, pulled up to 400', pumped 50 sx. cement, pulled to 40' and topped off with 10 sx. cement, 60/40 pos, 6% Gel, 12-17-01 Topped off with 55 sx. 60/40 pos, 6% gel, Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Berexco, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of December ~~XXX~~ 2001

My Commission Expires: _____

