

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Stafford County, Sec. 5 Twp. 21S Rge. 11W (E)(W)
Location as "NE/CNW/SW" or footage from lines N/2 SE/4
Lease Owner H. A. Chapman Investments
Lease Name Boyd #2 Well No. 2
Office Address 404 Cities Service Building, Tulsa, Oklahoma 74119
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 12, 1974 19
Application for plugging filed April 12, 1974 19
Application for plugging approved April 12, 1974 19
Plugging commenced 8:00 PM, April 12, 1974 19
Plugging completed 10:00 PM, April 12, 1974 19
Reason for abandonment of well or producing formation
Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3630' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	309'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Halliburton plug and 40 sacks cement at 500';
heavy mud to 300'; Halliburton plug and 25 sacks
cement. Heavy mud to 40', 15 sacks to surface;
2 sacks in rathole. Weld plate on top of surface pipe.

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1974
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sterling Drilling Company
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF Kansas, COUNTY OF Rice, ss.
F. A. Wuellner, (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) *F. A. Wuellner*
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

Subscribed and Sworn to before me this 17th day of April, 1974.



CHARLES HALL—NOTARY PUBLIC
My Commission Expires Jan. 6, 1978

Charles M. Hall
Charles M. Hall, Notary Public.

15.185.20495.0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- BOYD #2
Located: N/2 SE/4, Section 5-21S-14W, Stafford County, Kansas

OWNER: H. A. Chapman Investments
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 3, 1974
COMPLETED: April 12, 1974

TOTAL DEPTH: 3630'

<u>LOG</u>	
0 - 41	Clay
41 - 309	Sand and Shale
309 - 545	Shale
545 - 1135	Shale, Sand, Salt
1135 - 1980	Shale
1980 - 3370	Shale and Lime
3370 - 3536	Lime
3536 - 3628	Lime and Shale
3628 - 3630	Lime

CASING RECORD
Ran 7 joints new 8 5/8" casing, 299.10' set at 309' K.B. with 150 sacks 50/50 Pozmix, 2% gel and 3% cc. Plug down at 4:15 AM, 4-4-74.

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1974
CONSERVATION DIVISION
Wichita, Kansas

Plugged.