


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give all Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 So. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 5 Twp. 21 Rge. 14 (W)

Location as "NE/CNW/SW" or footage from lines S 2 SE NW
Lease Owner Wilkinson Drilling, Inc.
Lease Name Keeley Well No. 1
Office Address 805 Union Center
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/15/61 19 61
Application for plugging filed 3/15/61 19
Application for plugging approved 3/15/61 19
Plugging commenced 3/15/61 19
Plugging completed 3/15/61 19
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan, Russell, Kansas.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3635' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug @ 240', 1/4 sacks Hulls, 20 sacks Portland cement through drill pipe. Top plug @ 35', 1/4 sacks Hulls, 10 sacks cement, 2 sacks cement in Rat Hole. Completed and plug down @ 3:30 AM. 3/15/61

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1961
CONSERVATION DIVISION
Wichita, Kansas
5-18-1961

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Wilkinson Drilling, Inc.
Address 805 Union Center, Wichita 2, Kansas.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Walter M. Wilkinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson
805 Union Center - Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this May 15th day of May, 19 61

Carolyn J. Luerson
Notary Public.

My commission expires January 2, 1965.



15-185.12385.0000

WILKINSON DRILLING, INC.
805 UNION CENTER
WICHITA 2, KANSAS

May 16, 1961

DRILLERS LOG

Wilkinson Drilling, Inc.
KEELEY No. 1

S $\frac{1}{2}$ SE NW, Sec. 5-21S-14W
Stafford County, Kansas

Contractor:	Company Tools
Commenced:	March 7, 1961
Completed:	March 14, 1961
Total Depth:	3635'
Elevation:	1925 Kelly Bushing
Surface Casing:	8 5/8" @ 257' w/250 sx. cmt.

FIGURES INDICATE BOTTOMS OF FORMATIONS:

<u>Depth</u>	<u>Formation</u>
0 - 140	Sand and clay
140 - 260	Shale and shells
260 - 865	Red-bed shale
865 - 890	Anhydrite
890 - 1863	Shale and shells
1863 - 3242	Lime and shale
3242 - 3315	Shale
3315 - 3563	Lime
3563 - 3581	Chert
3581 - 3626	Shale and sand
3626 - 3635	Arbuckle Dolomite

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1961
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the drillers log on the Kelley No. 1, located in the S/2 SE/4 NW/4 of Section 5-21S-14W, Stafford County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson
Walter M. Wilkinson-Pres.

Subscribed and sworn to before me this 16th day of May, 1961.

Carolyn K. Iverson
Carolyn K. Iverson-Notary Public

My commission expires January 2, 1965.