

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

T - 21 NORTH R - 14W

	o		
	21		

Locate well correctly on above
Section Plat

Stafford County, Sec. 21 Twp. 21S Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines SE/4 NE NW
Lease Owner Frank J. Black (Gulf Oil Corporation)
Lease Name Marion Russell Well No. 2
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed July 10, 19 56
Application for plugging filed January 17 19 61
Application for plugging approved January 20 19 61
Plugging commenced January 18 19 61
Plugging completed January 21 19 61
Reason for abandonment of well or producing formation No longer economical to operate.

If a producing well is abandoned, date of last production June 28, 19 60
Was permission obtained from the Conservation Division or its agents before plugging-was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Viola Depth to top 3692 Bottom 3702 Total Depth of Well 3836 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	893'	None
				5 1/2"	3828'	2990'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back total depth was 3799'. Filled hole with sand to 3,680' and topped with 5 sacks of cement. Mudded hole to 300' and set 10' rock bridge. Inserted cement plug of 20 sacks. Mudded hole to 40' and set 10' rock bridge. Capped hole with 10 sacks of cement to surface. (Lease owned by Gulf Oil Corporation. Well No. 2 purchased by Frank J. Black for salvage.)

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1961

CONSERVATION DIVISION
Wichita, Kansas

3-29-1961

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Co. License #236
Address Box 572, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. V. Kersten (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. V. Kersten
316 Union Center Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of March, 19 61

My commission expires June 3, 1961
C. C. Lewis Notary Public.

15.185.10794.0000

MARION RUSSELL NO. 2

C SE NE NW Section 21-21S-14W
Stafford County, Kansas
Gulf Oil Corporation

8-5/8" O. D. casing cemented at 890'
5-1/2" O. D. casing cemented at 3836'

Drilling commenced June 13, 1956
Drilling completed June 27, 1956

FROM	TO	FORMATION	REMARKS
0'	185'	Sand	
185	325	Sand & clay	
325	500	Sand	
500	675	Red bed	
675	875	Red bed & shale	
875	905	Anhydrite	8-5/8" O. D. casing cemented at 890'
905	1465	Red bed and shale	
1465	1810	Shale & lime shells	
1810	1980	Lime & shale	
1980	2135	Shale & lime	
2135	2275	Lime & shale	
2275	2445	Shale & lime	
2445	2620	Lime & shale	
2620	2810	Shale & lime	
2810	3015	Shale	
3015	3130	Shale & lime	
3130	3718	Lime	
3718	3770	Chert	
3770	3780	Lime	
3780	3805	Sand & shale	
3805	3836	Lime & shale	5-1/2" O. D. casing cemented at 3836'
T.D. 3836'			

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1961
CONSERVATION DIVISION
Wichita, Kansas