

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kiowa SEC. 11 TWP. 282S RGE. 16 W E/W
Location as in quarters or footage from lines:
2310 FSL 2310 FWL

Lease Owner Texas Oil and Gas Corporation
 Lease Name Ross Well No. F-2
 Office Address Suite 300 - 200 W. Douglas
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas
 Date Well Completed 2-4-81
 Application for plugging filed 6-7-82
 Plugging commenced 6-12-82
 Plugging completed 6-17-82

Reason for abandonment of well or producing formation Dry

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom T.D. 4,852

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	436	None
				4 1/2"	4851	3111

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug back at 4,670
sand from 4,670 to 4,600
4 sacks cement from 4,600 to 4,580

Pumped in 5 sacks hull - 20 sacks jel -

150 sacks common cement - 3% C. C.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.
Edna R. Maggenster (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Edna R. Maggenster
Medicine Lodge, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of June, 1982

Jessie Hamilton
Notary Public.

My Commission expires: April 4, 1984

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1982
CONSERVATION DIVISION
Wichita Kansas

KANSAS DRILLERS LOG

15-097-20724-0000

COMPANY Texas Oil & Gas Corp.

SEC. 11 T. 28S R. 16W
LOC. NE NE SW

FARM Ross "F" NO. 2

COUNTY Kiowa

ROTARY TOTAL DEPTH 4,852'
COMM. January 22, 1981 COMP. January 31, 1981
CONTRACTOR H-30, INC. (Rig #5)
ISSUED February 4, 1981

CASING

10 3/4"
8 5/8" Set at 436' cemented w/400 sxs cement ELEVATION 2,122' K.B.
5 1/2"
4 1/2" Set at 4,851' cemented w/135 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed	456'
Red Bed, Shale and Anhydrite	1,475'
Red Bed and Shale	2,171'
Shale	2,376'
Shale and Lime	2,991'
Lime and Shale	3,230'
Shale and Lime	4,290'
Lime and Shale	4,490'
Shale and Lime	4,852'
Rotary Total Depth	4,852'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Gary Younger - V. President

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 4th day of February, 1981.

Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION
JUN - 9 1982
CONSERVATION DIVISION
Wichita, Kansas

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

15-097-20724-0000
 Phone Plainville 913-434-2812
 Phone Kiowa 316-825-4618

ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31

Russell, Kansas 67665

No 27838

Date	6-17-81	Sec.	11	Twp.	28	Range	10	Called Out	7:30 AM	On Location	9:00 AM	Job Start	9:30 AM	Finish	10:30 AM
Lease	ROSS	Well No.	F-2		Location			County	KIOWA		State	KS			

Contractor	
Type Job	Plugging
Hole Size	T.D.
Csg. Size	Depth
Tbg. Size	Depth
Drill Pipe	Depth
Tool	Depth
Cement Left in Csg.	Shoe Joint
Press Max.	600
Meas Line	Displace
Perf.	

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Charge To	TEXAS OIL & GAS CORP.
Street	
City	State
The above was done to satisfaction and supervision of owner agent or contractor.	
Purchase Order No.	
X	Saul A. Luthi State Pluggin

EQUIPMENT

No	Cementer	4000
Pumptrk 46	Helper	1277
No	Cementer	
Pumptrk	Helper	
	Driver	FORREST
Bulktrk 68		
Bulktrk	Driver	

Amount Ordered	150.438
Consisting of	
Common	150
Poz. Mix	
Gel.	200
Chloride	4
Quickset	
	Mull 5
Sales Tax	

CEMENT RECEIVED
 STATE CORPORATION COMMISSION
 JUN 22 1982
 CONSERVATION DIVISION
 Wichita, Kansas

DEPTH of Job

Reference:	Pump Truck	
	1.588 Plug	
	20 miles For Pump Truck	
	Sub Total	
	Tax	
	Total	

Handling	179
Mileage	70
Sub Total	
Total	
Floating Equipment	

Remarks: