

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER. 15-097-20,863 000

LEASE NAME ROSS 'F'

WELL NUMBER #3

2310' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 11 TWP. 28S RGE. 16 ~~XXXXX(W)~~

COUNTY Kiowa

Date Well Completed 3-24-82

Plugging Commenced 1-7-87

Plugging Completed 5-11-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR TXO Production Corp.

ADDRESS 155 N. Market, Suite 1000, Wichita, Kansas 67202

PHONE#(316) 269-7600 OPERATORS LICENSE NO. 5171

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? YES

Which KCC Office did you notify? Unknown

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4818'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	9 jts	
				4-1/2"	117 jts	57 jts

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Dumped 100 gals sand down perfs. Dumped 4 sxs cmt. Pulled & laid down 57 jts 4-1/2" csg.
Pumped 3 sxs hulls, 15 gel, 50 sxs 60/40 poz w/ 6% gel, 10 gel, 1 sx hulls, 8-5/8" plug, 100 sxs 60/40 poz w/ 6% gel. Max pressure=700 psig. ISIP=350 psig.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Box 108, Attica, KS. 67009

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jeffrey S. Childs

(Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jeffrey S. Childs

(Address) 155 N. Mkt, Ste 1000, Wichita, KS. 67202

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 87

Commissioner Koehler
 STATE CORPORATION COMMISSION

My Commission Expires: July 10, 1988

MAY 13 1987
 5-13-1987
 CONSERVATION DIVISION
 Wichita, Kansas

Form CP-4
 Revised 07-86