


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barton County, Sec. 1 Twp. 16 Rge. 13W (X) (W)

Location as "NE/CNW&SW" or footage from lines SE NW NE
Lease Owner K & E Drilling Inc.
Lease Name Rude "D" Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 4-19-62 19____
Plugging completed 4-21-62 19____
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3360 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	407'	None
				5-1/2"	3360'	2636'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 2960', sanded to 2910' and dumped 5 sacks of cement @ 2910' with dump bailer. Pulled 5 1/2 casing to 550' and pumped in 10 sacks of fell mud, pulled casing to 400', and pumped in 15 sacks of cement @ 400'. Pulled casing to 300' and pumped in 20 more sacks of cement. Pulled balance of 5 1/2" casing, bailed fluid to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1962

CONSERVATION DIVISION
Wichita, Kansas

9-28-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1962

Milton J. Volin
Notary Public.

My commission expires May 20, 1964



DRILLER'S LOG

OPERATOR:	K & E DRILLING, INC. 719 Union Center Wichita 2, Kansas	FARM NAME:	#1 RUDE 'D' LEASE
CONTRACTOR:	K & E DRILLING, INC. 719 Union Center Wichita 2, Kansas	LOCATION:	SE 1/4 NE Sec. 1-16S-13W Barton Co, Kansas
CASING:	8-5/8" @ 407 (250 sx) 5-1/2" @ 3360 (125 sx) & DV @ 860 Cmtd in.	COMMENCED:	12-18-57
R.T.D.	3361'	COMPLETED:	12-28-57
		ELEVATION:	1897' KB
		PRODUCTION:	OIL - LANSING

FORMATION RECORD

Depths shown indicate bottom of formations encountered

Shale & Shells	105
Sand	200
Hard Sand & Shale	260
Shale & Shells	407
Hard Sand & Shale	550
Shale	725
Shale & Shells	833
Anhydrite	863
Shale & Shells	1475
Lime & Shale	1713
Shale & Lime	1940
Lime & Shale	2520
Shale & Lime	2675
Lime & Shale	2880
Lime	2895
Lime & Shale	2983
Shale & Lime	2990
Lime & Shale	3003
Toroate	3017
Douglas	3029
Sand & Shale	3070
Lime	3361
R.T.D.	3361

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1962

CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

STATE OF KANSAS)
) SS:
COUNTY, OF SEDGWICK)

I, Dale Silcott, of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the K & E #1 RUDE 'D' well.

Dale Silcott
Dale Silcott

Subscribed and sworn to before me this 13th day of January, 1958.

John M. Edwards
John M. Edwards, Notary Public

My commission expires: 11 August 1958.