


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

~~XXXXXXXX~~ BARTON County. Sec. 1 Twp. 16 Rge. 13 (E) W (W)



Locate well correctly on above
Section Plat

Location as "NE/CNW&SW" or footage from lines SW NW NE
Lease Owner SPECTER PIPE & SUPPLY,
Lease Name RUDE "D" Well No. 2
Office Address
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 6-19-58 19
Application for plugging filed Dec. 16, 1965 19
Application for plugging approved Dec. 17, 1965 19
Plugging commenced December, 17, 1965 19
Plugging completed December, 22, 1965 19
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production Dec 19 65
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truman Russell, Kansas
Producing formation Kansas City Depth to top 3076 Bottom 3331 Total Depth of Well 3355 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	360 ft.	none
				7" OD	3353 ft.	1815 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged, back with sand to 3000-feet, dumped 5- sacks cement.
Set a Rock Bridge at 350- feet, dumped 30- sacks cement,
Mudded hole up to -35- feet, dumped ten sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1965

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor LYNCH CASING PULLING, COMPANY. NO. 457
Address R.Rt. 4 GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.
_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Walter Specter*

(Address)

SUBSCRIBED AND SWORN to before me this 24th day of December, 19 65

My commission expires December 1, 1968

Elsie Coady
Elsie Coady Notary Public.

15-009-16142-00-00

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. K & E DRILLING, INC.,
Farm. Ruder "D"
No. 2

SEC. 1 T. 16 R. 13W
SW NW NE

Total Depth. 3355'
Comm. 6-10-58 Comp. 6-19-58
Shot or Treated.
Contractor. K & E Drilg.,
Issued. 4-11-59

County Barton
KANSAS



CASING:

8 5/8" 360' cem w/175 sx.
7" 3353' cem w/145 sx.

Elevation. 1893' KB

Production. 78 BOPD

Figures indicate Bottom of Formations.

shale	190
shale & redbed	360
shale	480
sand & shale	545
shale	815
red bed	835
Anhydrite	865
shale & shells	1365
shale & lime	1720
lime & shale	1860
lime	1995
lime & shale	2785
lime	3980
lime & shale	3070
lime	3355 RTD
Total Depth	

TOPS: SCOUT	
Anhydrite	835
Topeka	2702
Heebner	2976
Toronto	2992
Douglas	3008
Brown Lime	3061
Lansing	3076
Conglomerate	3332

DEC 17 1965