

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 1 Twp. 16S Rge. 13W 1/4/1/4
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
50' East of C NW/4 SW/4

Lease Owner L. G. Stepheons & Co., Inc.
Lease Name Harper-Rude Well No. 1
Office Address 7701 East Kellogg, Wichita, Ks. 67207
Character of Well (Completed as Oil, Gas or Dry Hole) D & A


Date Well completed November 7, 1980
Application for plugging filed November 7, 1980
Application for plugging approved November 7, 1980
Plugging commenced November 7, 1980
Plugging completed November 7, 1980

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane L. Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,395'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	305'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole @ 540' w/50 sx cement
@ 240' w/25 sx cement
@ 40' w/10 sx cement
5 sx cement in rathole

11-18-1980
RECEIVED
WICHITA COUNTY OFFICE
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
1720 KSB&T Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick
Gloria Fawcett contractor
(employee of ~~owner~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 KSB&T Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1980.

Joyce A. Baer
Notary Public.

My commission expires _____



15-009-22129-00-00

DRILLERS LOG

No. 1 Harper-Rude

CASING RECORD: 8 5/8" @ 312' w/185 sx cement
 D & A
 TOTAL DEPTH: 3,395'

COMPANY: L. G. Stephenson & Co., Inc.
 CONTRACTOR: Red Tiger Drilling Company
 COMMENCED: October 31, 1980
 COMPLETED: November 7, 1980

DESCRIPTION: 50' E of C NW/4 SW/4 Sec. 1-T16S-R13W Barton County, Kansas
 ELEVATION: 1,904' GR

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	115	
Shale	115	854	
Anhydrite	854	884	
Shale, Salt & Shells	884	1460	
Shale	1460	1760	
Lime & Shale	1760	2018	
Shale & Lime	2018	2470	
Lime & Shale	2470	2980	
Lime	2980	3075	
Lime & Shale	3075	3152	
Lime	3152	3269	
Lime & Shale	3269	3304	
Lime	3304	3395	
RTD		3395	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 12th day of November, 1980.

Joyce A. Baer
Notary Public

