

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

**Locate well correctly on above
Section Plat**

Barton County, Sec. 2 Twp. 16S Rge. 13 (X) (W)
 Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE $\frac{1}{4}$ NE $\frac{1}{4}$
 Lease Owner John A. Trimmell et al
 Lease Name Rude Well No. 1
 Office Address Great Bend, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed August 4 1950
 Application for plugging filed August 5 1950
 Application for plugging approved August 5 1950
 Plugging commenced August 5 1950
 Plugging completed August 5 1950
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....Yes.....

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... 3394' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to feet for each plug set.

Filled with heavy mud to 190'. Set plug.
Run 15 sacks cement through drill pipe to 190'.
Filled with mud to 30'. Set plug. Run 10 sacks
cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Sterling Drilling Company
Address.....Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Rollin Mead (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Sterling, Kansas

(Address)


SUBSCRIBED AND SWORN to before me this 8th day of August, 1950

My commission expires My Commission Expires Sept. 17, 1953

28-8278-S

4-50-10M

Notary Public.



RE

CONFIDENTIAL

AUG 10 1950

STATE CORPORATION
COMMISSION
KANSAS

15-009-05045.00-00

STERLING DRILLING CO.

STERLING, KANSAS

WELL LOG ----- RUDE NO. 1

Location - NEc NE/4 NE/4 of Section 2-16S-13W, Barton County, Kansas.

Owner - John A. Trimmell et al
Contractor - Sterling Drilling Company

Commenced - 7-24-50
Completed - 8-4-50 (w/r)

Elevation: 1900 DF
1898 Gr

Total Depth - 3394' (w/r)

LOG

0- 100	Clay
100- 200	Shale and Shells
200- 465	Shale and Sand
465- 860	Shale, Sand and Red Bed
860- 890	Anhydrite
890-1235	Shale
1235-1475	Shale and Red Bed
1475-1585	Shale and Shells
1585-1755	Lime and Shale
1755-1985	Lime
1985-2440	Lime and Shale
2440-2570	Shale and Shells
2570-2655	Shale
2655-2995	Lime
2995-3092	Lime and Shale
3092-3102	Brown Lime
3102-3115	Kansas City Lime
3115-3320	Lime
3320-3352	Shale
3352-3374	Conglomerate
3374-3394	Arbuckle Lime


CASING RECORD

200 Feet of 8-5/8" Surface Pipe
Cemented with 110 Sacks Cement

FORMATION TOPS

Heebner Shale	3010'
Brown Lime	3092'
Kansas City Lime	3102'
Conglomerate	3351'
Arbuckle Lime	3374'

PRODUCTION: Dry and Abandoned



RECEIVED
AUG 10 1950
ST. LOUIS
COMMISSION
KANSAS