

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-097-20,863 - 0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO Production Corp. OPERATORS LICENSE NO. 5171
ADDRESS 155 N. Market, Suite 1000, Wichita, Ks. 67202 PHONE # (316) 269-7600
2310' FSL &
LEASE (FARM) Ross 'F' WELL NO. #3 WELL LOCATION 330' FEL COUNTY Kiowa
SEC. 11 TWP. 28S RGE. 16 or TOTAL DEPTH 4818' PLUG BACK TD 4818'

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8-5/8" SET AT 415' CEMENTED WITH 350 SACKS
CASING SIZE 4-1/2" SET AT 4817' CEMENTED WITH 200 SACKS
PERFORATED AT 4655-60'; CLBP @ 4610'; 3546-48' (squeezed w/ 250 sxs); 3484-89'.

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plug perfs w/ 10 sxs cement. Cut 4-1/2" csg at 2800' and pull. Fill hole w/ mud to 475' & dump 30 sxs cement. Fill hole to 40' & dump 10 sxs cement.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? YES
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Jerry W. Collins PHONE # (316) 886-5606

ADDRESS R.R. #1, P.O. Box 125-B, Medicine Lodge, KS. 67104

PLUGGING CONTRACTOR Clarke Oilfield Services LICENSE NO. 5105

ADDRESS 107 W. Fowler, Medicine Lodge, KS. 67104 PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Charles A. Paulson
(Operator or Agent)

NOV 21 1986
11-20-1986 DATE: November 18, 1986

①



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

FEB 20 '87

EXPIRES

November 20, 1986

WELL PLUGGING NOTICE

Ross "F" #3
2310'FSL 330'FEL
Sec. 11-28S-16W
Kiowa County

TXO Production Corporation
155 N. Market, Ste. 1000
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in dark ink, appearing to be "J. McCord".

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).