

4
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15.185.30179.0000

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Lee Phillips Oil Co. & Graves Drilling Co., Inc.

Complete Address: 1532 Wichita Plaza, Wichita, Kansas

Lease Name McGinty Well No. # 1

Location NE SE SW Sec. 36 Twp. 21 Rge. 14 (E) W

County Stafford Total Depth 3307'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Graves Drilling Company, Inc.

Address: 412 Union Center, Wichita, Kansas License No.

Operation Completed: Hour 10:00AM Day 24th Month Oct. Year 1965

The Above well was plugged as follows:

320' of 8 5/8" surface pipe, cement circulated with 350 sacks. Fluid level in the hole was at 230'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 260', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged solid with hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Achie Elving
Well Plugging Supervisor

INVOICED

DATE 10/28/65

INV. NO. 3054-11