

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 4 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply Inc

Complete Address Box 169 Russell, KS

Lease Name Keenan Well No. 1

Location NE/SW/NW Sec. 36 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3801

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Pipe Pullers Inc

Address Box 486 Ellinwood, KS License No. 462

Operation Completed: Hour 10:00 AM Day 31 Month 8 Year 1973

The above well was plugged as follows:

209 ft 8 5/8 surface cemented with 200 sacks. 3800 ft 4 1/2 long string  
cemented with 125 sacks. Top perf. 3592 ft. Sand to 3565 ft, 4 sacks  
cement with bailer. Pulled 2000 ft 4 1/2. Pump 2 sacks hulls, 10 sacks  
gel, 100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: A. Russell Bikerstein  
Well Plugging Supervisor

INVOICED

DATE 9-4-73

INV. NO. 7877-10