

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1963

CONSERVATION DIVISION  
Wichita, Kansas

11-1-1963

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Bowers Drilling Co.

Complete Address: 416 Union Center, Wichita, Kansas

Lease Name McGinty Well No. # 1

Location C S/2 NE SE Sec. 36 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3770

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Bowers Drilling Co.

Address: 416 Union Center, Wichita, Kansas License No.     

Operation Completed: Hour: 3:30AM Day 31st Month Oct. Year 1963

The Above well was plugged as follows:

314' of 8 5/8" surface pipe, cemented with 450 sacks. Fluid level was  
up in hole. 1st cementing plug and 1/4 sack hulls was pushed to 275,  
cemented with 25 sacks, through drill pipe. Hole was filled with drill-  
ing mud to 40', 2nd cementing plug, bridged with 1/2 sack hulls, cemented  
with 10 sacks to base cellar. Rat hole bridged and cemented with 2 sacks.  
This cementing job was done by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 11/1/63  
INV. NO. 8004-u

Signed: Archie Elving  
Well Plugging Supervisor