

5

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 138-14

LOCATION Sec-21E-22W

SEC. 26 TWP. 21 RGE. 14-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Heenan "D"

Operator Petroleum, Inc. Address 700 Noeby Bldg. Wichita-Kans.

Field _____ County Stafford

Total Depth 3826 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 200ft. Circulated with cement.
Shoe string set at 3642ft. 75 sacks of cement - Plugged
back to 3590ft with cement - sand to 3550ft - dumped
5 sacks of cement at 3550ft - ripped off & pulled the shoe string
and to 200ft - Set Rock Bridge x 15 sacks of
cement at 200ft - mud to 35ft - Bridge &
10 sacks of cement at the release.

Bill Morgan - Plugging Contractor

2-5-1952

FEB 5 X 1952
C. W. Stoenck -
District Conservation Agent

PLUGGING
FILE SEC 36 T 21 R 14W
BOOK PAGE 138 14

Date 2-2-52