

15.185.10797.0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

OCT 1 1970

CONSERVATION DIVISION  
Wichita, Kansas

10-1-1970

Operator's Full Name D.R. Lauck Oil Co. Inc.

Complete Address 301 S. Broadway Wichita, Ks

Lease Name Titus Well No. 3

Location NE/NW/NE Sec. 21 Twp. 21 Rge. 14 (E) (W)<sup>W</sup>

County Stafford Total Depth 3703

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Glenn & Smith Pipe Pullers

Address 204 E. 6th Ellinwood, Ks License No. 396

Operation Completed: Hour 9:30 AM Day 29 Month 9 Year 1970

The above well was plugged as follows:

862 ft of 8 5/8 surface pipe cemented with 400 sacks. 3703 ft of  
5 1/2 long string cemented with 100 sacks. Top perf. 3624 ft. Sand  
back to 3600 ft, 5 sacks cement with bailer. Pulled 3108 ft of 5 1/2.  
Set 10 ft rock bridge at 350 ft. Fill hole with 5 yds of redimix  
to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. Russell Babin  
Well Plugging Supervisor

DATE 10-1-70

INV. NO. 2609-U