

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 75-30 Location: CNW - NW - SE
County: STAFFORD Sec. 21 Twp. 21 Rge. 14 (EX) (W)
Name of Field or Pool: _____ Total Depth: 3865

I have this date completed supervision of plugging of:

Well No. 1 Lease BLEDSE-HEIRS
Operator's Full Name GULF OIL CORPORATION % A.L. LATTA
Complete Address: BOX 2233 WICHITA, KANS
Plugging Contractor: C.E. SHULL
Address: GT BETO, KANS License No. 8
Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____
If well is a rotary drilled dry hole did operators wait for you to arrive _____
If yes how long _____ Reason: _____

Operation Completed: Hour 9:30^{AM} Day 11 Month 2 Year 1958

The above well was plugged as follows:

8 3/4 SURFACE PIPE 864' - W/670 5X CMT - 5 1/4 3844'
TOP PERFORATION 3700' - SANDED BOTTOM OF HOLE
TO 3690 - 5 SX CMT PLUG THROUGH BAILER - PULLED
PIPE - FILLED HOLE W/HVY MUD TO 300' - SET ROCK
BRIDGE W/20 SX CMT - FILLED HOLE W/HVY MUD
TO 35' - SET ROCK BRIDGE - CAPPED TO BASE OF
CELLAR W/10 SX CMT

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: Frank Bradford
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Reviewed: J Lewis Brock Signed: _____
Field Supervisor Well Plugging Supervisor

Remarks:

PLUGGING	
FILE SEC. <u>21</u> T. <u>21</u> R. <u>14</u>	
BOOK PAGE <u>75</u> LINE <u>20</u>	

2-18-1958