

15-009-16141-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

4-25-1962

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1962

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Barton

Location: SE NW NE Sec. 1 Twp. 16 Rge. 13 (E) _____ (W) _____

Name of Field: _____ Total Depth: 3360

I have this date completed supervision of plugging of:

Lease Name: Rude Well No. 1

Operator's Full Name: K.&E. Drilling, Inc.

Complete Address: 719 Union Center, Wichita, Kansas

Plugging Contractor Knight Casing Pulling Co.

Address: Box 403, Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3:00 PM Day 21 Month 4 Year 1962

The above well was plugged as follows:

8 5/8" 407' Gwc.

Sanded hole back to 2910' & dumped 5 sax cement with dump bailer.

Pulled pipe. Circulated hole with mud @ 550'. Pulled pipe to 400', &

displaced 15 sax cement thru pipe. Pulled pipe to 300' & displaced

20 sax cement thru pipe with mud pump. Pulled remaining pipe. Set

rock bridge @ 40' & displaced 10 sax cement, cementing to base of

cellar.

Signed: Dore Truman
Conservation Division Agent

Reviewed: Harold J. Hollis
Field Supervisor

Remarks:

INVOICED

DATE 5/10/62

INV. NO. 4910-w