

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,448-0000

LEASE NAME Amber/Beran

WELL NUMBER 2

SPOT LOCATION SW NW SW

SEC. 34 TWP. 16 RGE. 12 (X) or (W)

COUNTY Barton

Date Well Completed 6-8-84

Plugging Commenced 6-8-84

Plugging Completed 6-8-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Amber Oil Company

ADDRESS Su.360-Three Corporate Plaza Oklahoma City, OK 73112

PHONE # (405) 842-8634 OPERATORS LICENSE NO. 6425

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Gilbert Balthzor

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3360'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 780' w/25 sacks cement thru drill pipe
Next Plug: @ 550' w/80 " " " " "
Next Plug: @ 320' w/40 " " " " "
Top Plug: @ 40' w/1/2 sack hulls & 10 sacks cement
10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929
Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson
(Address) Box 823 Great Bend, KS 67530

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1984

SUBSCRIBED AND SWORN TO before me this 11 day of June, 1984

STATE CORPORATION COMMISSION
Wichita, Kansas

Deborah M. Hague
Notary Public

My Commission expires: 4-29-86

15-009-23448-00-00

DRILLER'S WELL LOG

DATE COMMENCED: June 3, 1984
DATE COMPLETED: June 8, 1984

Amber Oil Company
AMBER/BERAN #2
SW NW SW
Sec. 34, T16S, R12W
Barton County, Ks.

ELEVATION: 1878 K.B.

0 - 751' Surface Soil, Shale, Sand,
Red Bed
751 - 777' Anhydrite
777 - 2649' Lime & Shale
2649 - 2675' Lime
2675 - 2685' Shale & Sand
2685 - 2968' Lime
2968 - 2972' Shale
2972 - 2984' Lime & Shale
2984 - 2995' Lime
2995 - 3057' Shale
3057 - 3072' Lime & Shale
3072 - 3319' Lime
3319 - 3360' Shale, lime, Chert, Sand
3360' RTD

FORMATION DATA

Anhydrite	751'
Howard	2649'
Severy	2675'
Topeka	2685'
Heebner	2968'
Toronto	2984'
Douglas	2995'
Gr. Lime	3057'
Kansas City	3072'
Base K.C.	3319'
Conglomerate	3326'
RTD	3360'

Surface Pipe: Set used 8-5/8"
28# pipe @326' w/170 sacks
50/50 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 11th day of June 1984.

My Comm. Expires:

4-29-86

Dorothy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1984
CONSERVATION DIVISION
Wichita, Kansas