

WILLIAMS, P. L. GOING, RECORD)

Barton _____ County _____ 34 Twp. _____ 16S _____ 12 (W)

Location as "NE CNW&SW" etc. Page from book _____ NW NE NW _____
 Owner Jay Bergman Oil Company _____
 Well Name Tinkel _____ Well No. 1 _____
 Well Address 425 Union Center Bldg., Wichita 2, Kansas _____
 Character of Well (completed as Oil, Gas or Other) _____ oil well _____
 Well completed _____ May 19 _____ 1950 _____
 Application for plugging filed _____ May 6 _____ 1961 _____
 Application for plugging approved _____ May 6 _____ 1961 _____
 Plugging commenced _____ May 6 _____ 1961 _____
 Plugging completed _____ May 6 _____ 1961 _____
 Use of well for abandonment of well or producing formation _____ non-commercial _____

[illegible]

Name of Conservator Agent who accompanied you	Don Truan	
Producing formation	Depth to top	Total Depth of well
Show depth and thickness of all water bearing gas formations		

OIL, GAS OR WATER RENT OR

CLASSIC 11 3D

FORMATION

CONTENTS

Figure 1

SIZE
5 1/2

01-14

2500

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud hole to 250 feet, 10 ft. rock bridge, dump 25 sax cement.
Mud to 40 feet, 10ft. rock bridge, dump 10 sacks cmenet.

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1962
CONSERVATION DIVISION
MICHIGAN, Kansas

Name of Plugging Contractor Wilson, Inc.
Address 317 No. Buffalo, Stafford, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.

Harold Bergman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and numbers herein contained as in the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Bergman
425 Union Center Bldg., Wichita 2, Kansas

SUBSCRIBED AND SWORN to before me this 6th day of May, 1961

My commission expires August 2, 1962

BERGMAN OIL COMPANY

UNITED NATIONAL BANK BUILDING

WICHITA

KANSAS.

GEOLOGICAL DATA:

Tinkle No. 1. NW NE NW Sec. 34-16-12 West, Barton County, Kansas.

Note: All depths measured from derrick floor.

Elevation: 1891' (derrick floor)

Lansing (White lime) 3079' (-1188)

Soft horizons in Kansas City:

3156' - 3155' Dolomite and calcareous, chalky, porosity poor, no odor, no show.

3270' - 3275' Porosity poor, no odor, no show.

Conglomerate 3323' (-1132) Tricolored sandstone and lime, some chert.

Arbuckle 3336' (-1115) Dolomite, white, dense, some porosity, no saturation, no odor..

Total Rotary Depth 3341' 5 1/2" set on bottom.