

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barton County. Sec. 34 Twp. 16 Rge. 12 (E) W (W)

Location as "NE/CNWSW" or footage from lines. NW SE NE

Lease Owner Shields Oil Producers Inc.

Lease Name Jenisch Well No. 2

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed September 15, 19 55

Application for plugging filed August 22, 19 69

Application for plugging approved August 25, 19 69


Plugging commenced Oct. 7 19 69

Plugging completed Oct. 21 19 69

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3346 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8"	165'	Cmtd. w/100 sax
				4 1/2"	3,322'	445'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3346 feet to SURFACE feet for each plug set.

Set bridge at 2950' dump 4 sacks of cement on bridge. Pipe came into at 445.00'. Plug hole Pump 20 sacks of mud & 90 sacks of cement in hole with pump truck.

Well completed.

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.

Address P.O. Box 313 Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

R. J. Shields

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R. J. Shields
Shields Bldg., Russell, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 69

Luth Phillips

Notary Public.

My commission expires May 26, 1971



Shields


Russell, Kansas

WELL LOG

15-009-07414-00-00

Operator: Shields Oil Producers
 Well: Jenisch #2
 Commenced: September 4, 1955
 Completed: September 15, 1955
 Contractor: Shields Drilg. Co., Inc.

Well Description: NW SE NE



Sec. 34-16-12W
 Barton County, Kansas

CASING RECORD

Size	Run	Pulled
8 5/8"	165'	Cmtd. with 100 sax
4 1/2"	3322'	Cmtd. with 200 sax

Elevation: 1879' RB
 Treatment: 1,000 gal. acid

Production: 25 BOPD

Tops:

Topeka	2665'
Hoebner	2948'
Toronto	2964'
Douglas	2965'
Brown	3037'
Wans: K. G.	3053'
Arbuckle	3319'

..... Figures Indicate Bottom of Formations

Top Soil Limestone	40
Sand	80
Shale	162
Shale & Sand Streaks	505
Red Bed	550
Red Bed & Shale	760
Anhydrite	805
Red Bed & Shale	920
Shle. & Shells	985
Shale & Shell Strks. Salt	1045
Shells & Salt	1135
Shale & Shells	1315
Shale & Limestone	1515
Lime & Shale	1880
Lime	2020
Lime & Shale	2110
Shale & Lime Streaks	2250
Shale & Shells	2440
Shale & Lime Streaks	2560
Shale & Lime	2670
Lime	3322
Arbuckle Dolomite	3325 RTD

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 25 1966
 CONSERVATION DIVISION
 Wichita, Kansas

1-27-64

Set bridge plug at 3, 114'; perforated 16 holes at 3, 104'-3, 108'; 12 holes at 3, 089'-3, 092' and 40 holes at 3, 064'-3, 074'. Acidized with 3, 000 gallons.

DST#1-3055-90 Gas to surface in 22 min. Tool open 1 hr. with good blow. Recovered 80' Oil & gas cut mud, 180' very heavily oil & gas cut mud, 240' free oil. 1FF-0# FFP-130# BHP-1050#

Completion-Drill Plug. Show oil. Drill deeper 3326'. 12 hr. fillup 125' Oil. Squeeze shoe. Acidize with 1,000 gal. with Dowell Electric Pilot. Swabbed 20 BOPH/5 hrs. POP

Notes