STATE OF KANSAS
STATE CORPORATION COMMISSION

15-009-06576-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Barton County. Sec. 34 Twp. 16 Rge. 12 (E) W (W)

Location as "NE/CNW¼SW¼" or footage from lines SW NW NE

Lease Owner Shields Oil Producers

Lease Name Feltes Well No. SWDW

Office Address Shields Building, Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) SWDW

Date well completed January 22 19 56

Application for plugging filed June 9 19 59

Application for plugging approved June 9 19 59

Plugging commenced June 9 19 59

Plugging completed June 9 19 59

Reason for abandonment of well or producing formation Salt water disposal plugged up, would not take water

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation Depth to top Bottom Total Depth of Well 3525 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	Cmtd. w/100 sax
				4 1/2"	3410'	Cmtd. w/100 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill w/heavy mud to 250'
Set bridging plug @ 250' w/1/2 sax hulls on plug
Dump 35 sax cement on plug thru drill pipe
Fill w/heavy mud to 55' w/1 sax hulls on plug
Dump 10 sax cement to cellar

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Company, Inc.

Address Shields Building, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. J. Shields

(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 1959

Harriet V. Peterson
Notary Public.

My commission expires March 6, 1961

24-7368-S 3-53-20M

PLUGGING
FILE SEC 34 T 16 R 12W
BOOK PAGE 45 LINE 11

Shields

Russell, Kansas

WELL LOG

Operator: Shields Oil Producers
Well: Feltes #2
Commenced: January 10, 1956
Completed: January 22, 1956
Contractor: Shields Drilling Co., Inc.

Well Description: SW NW NE
Sec. 34-16-12W
Barton County, Kansas



Elevation: 1895' RB
Treatment:

Production: SWDW

CASING RECORD

Size	Run	Pulled
8 5/8"	250'	cmtd /100 sax
4 1/2"	3410'	cmtd /100 sax

Tops:

Heebner	2970'
Toronto	2987'
Brown Lime	3060'
Lans-KC	3077'
Ch. Congl.	3337'
Arbuckle	3367'
Sand	3524'

.....Figures Indicate Bottom of Formations....

Surface Clay	50
Lime Streaks & Shale	200
Shale	360
Sand	510
Red Bed	780
Anhydrite	810
Red Bed & Shale	1050
Shale-Shells & Salt	1295
Shale & Shells	1420
Lime & Shale	1515
Shale & Lime	1615
Lime & Shale	1735
Shale & Lime	1865
Lime & Shale	1970
Lime	2030
Lime & Shale	2160
Shale	2647
Shale & Lime	2728
Lime & Shale	2856
Lime	3013
Shale & Lime	3100
Lime	3525 RTD

PLUGGING
FILE SEC 34 T 16 R 12W
BOOK PAGE 45 LINE 11

Notes

DST #1 - 3080 - 3140 Tool open 1 hr. Weak steady blow. Received 80' muddy water.
IFF -0#, FFP-40#, BHP - 865#/20 min.

NOTE: Lost circulation @3525'