

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County. Sec. 35 Twp. 16 Rge. (E) 12 (W)

Location as "NE/CNW*SW*" or footage from lines SE/SE/NE

Lease Owner Tennessee Gas Transmission Co.

Lease Name Lydia Harzman Well No. 1

Office Address P. O. Box 513 Chase, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-27 19 57

Application for plugging filed 3-27- 19 57

Application for plugging approved 3-27 19 57

Plugging commenced 3-27 19 57

Plugging completed 3-27 19 57

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	270'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 300'. Set bottom plug with 5' rock bridge and 25 sacks cement through drill pipe. Filled hole to 20'. Set top plug with 1/2 sack hulls, and cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company

Address 915 Union Center Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. Fred Hambright (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambright

915 Union Center Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29th day of March, 19 57

A. R. Derrington Notary Public.

My commission expires 8-20-57

PLUGGING
FILE SEC. 35 T. 16 R. 12 W
BOOK PAGE 2 LINE 36

RECEIVED
APR 3 - 1957
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

15-009-01300-00-00

COMPANY Tennessee Gas Transmission Co.


SEC. 35 T. 16 R. 12W

FARM Lydia Harzman NO. 1

LOC. SE/SE/NE

TOTAL DEPTH 3435'
COMM. 3-15-57 COMP. 3-27-57
SHOT OR TREATED
CONTRACTOR Lewis Drilling Company
ISSUED

COUNTY Barton
KANSAS



ELEVATION 1940 R.B.

PRODUCTION

CASING

20 10
15 8 5/8" - 270'
12 6
13 5

FIGURES INDICATE BOTTOM OF FORMATIONS

0-40	Surface soil & Clay
40-70	Shale
70-185	Sand & Shale
185-385	Shale & Red Beds
385-472	Sand
472-490	Anhydrite
490-780	Red Bed & Shale
780-1925	Shale & Lime
1925-2085	Lime
2085-2100	Sand
2100-2295	Lime
2295-2785	Shale & Lime
2785-3370	Lime
3370-3417	Conglomerate
3417-3435	Arbuckle Lime
3435	Total Depth

Geologic Tops

Topeka	2732
Heebner	3017
Douglas	3046
Kansas City	3136
Conglomerate	3370
Arbuckle	3416

State of Kansas }
County of Sedgwick } ss:

PLUGGING
FILE SEC. 35 T. 16 R. 12W
BOOK PAGE 2 LINE 36

I, J. Fred Hambright of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Lydia Harzman #1 well.

J. Fred Hambright
J. Fred Hambright
CORPORATION COMMISSION

Subscribed and sworn to before me this 29th day of March 19 57

My Commission Expires: 8-20-60

A. R. Derrington
A. R. Derrington
KANSAS