

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Barton

County. Sec. 35 Twp 16S Rge. 12 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NW

Lease Owner Larry Moore

Lease Name Korkish Well No. 2

Office Address Box 188, McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed October 31, 1952 19

Application for plugging filed October 31, 1952 19

Application for plugging approved October 31, 1952 19

Plugging commenced October 31, 1952 19

Plugging completed October 31, 1952 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

C. D. Stough

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3423 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	305	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole full heavy mud to 305 feet of top

and drove wooden plug to 305 feet. Dumped in

20 sacks of cement and finished filling hole with

heavy mud to within 35 feet of cellar. Dumped in

5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallard Drilling Company

Address 1016 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. C. Nelson, partner, Mallard Drlg. (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. C. Nelson

(Address)

SUBSCRIBED AND SWORN to before me this 28th day of Nov. 1952

My commission expires 12/4/52

Notary Public. [Signature]

PLUGGING  
FILE SEC 35 T 16 R 12  
BOOK PAGE 56 LINE 29

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 29 1952 11-29-1952  
CONSERVATION DIVISION

COMPANY: Larry Moore  
 CONTRACTOR: Mallard Drilling Company  
 FARM: Korkish #2  
 LOCATION: NE NW Sec. 35-16-12  
 Barton County, Kansas  
 COMMENCED: October 21, 1952  
 COMPLETED: October 31, 1952

0	to	235	Sand and shale
235	to	306	Red Bed
306	to	805	Shale and red bed
805	to	1260	Shale
1260	to	1565	Sand and lime
1565	to	1710	Lime
1710	to	1845	Lime
1845	to	1940	Lime and sand
1940	to	2065	Lime
2065	to	2185	Lime and shale
2185	to	2350	Lime and shale
2350	to	2490	Lime and shale
2490	to	2600	Lime
2600	to	2735	Lime
2735	to	2820	Lime
2820	to	3050	Lime
3050	to	3285	Lime
3285	to	3398	Lime
3398	to	3423	Arbuckle
		3423	T.D.

Set 305 feet of 8 5/8 inch surface pipe. Cemented with 160 sacks cement.

TOPS: Arbuckle -- 3398

Measurements taken from derrick floor.

DRY, ABANDONED AND PLUGGED

RECEIVED  
 STATE COMMISSIONER OF GEOL. & MINES  
 NOV 14 1952

C E R T I F I C A T E

CONSERVATION DIVISION  
 Wichita, Kansas

I, G. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Korkish #1, Sec. 35-16-12, Barton County, Kansas, as reflected by filed of the Mallard Drilling Company.

*G. C. Nelson*

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 6th day of November 1952.

*Appointed Wright*

My commission expires 12/4/52

COMPANY: Larry Moore  
 CONTRACTOR: Mallard Drilling Company  
 FARM: Korkish #2  
 LOCATION: NE NW Sec. 35-16-12  
 Barton County, Kansas  
 COMMENCED: October 21, 1952  
 COMPLETED: October 31, 1952

0	to	235	Sand and shale
235	to	306	Red Bed
306	to	805	Shale and red bed
805	to	1260	Shale
1260	to	1565	Sand and lime
1565	to	1710	Lime
1710	to	1845	Lime
1845	to	1940	Lime and sand
1940	to	2065	Lime
2065	to	2185	Lime and shale
2185	to	2350	Lime and shale
2350	to	2490	Lime and shale
2490	to	2600	Lime
2600	to	2735	Lime
2735	to	2820	Lime
2820	to	3050	Lime
3050	to	3285	Lime
3285	to	3398	Lime
3398	to	3423	Arbuckle
		3423	T. D.

Set 305 feet of 8 5/8 inch surface pipe. Cemented with 160 sacks cement.

TOPS: Arbuckle -- 3398

Measurements taken from derrick floor.

DRY, ABANDONED AND PLUGGED

**PLUGGING**  
 FILE SEC 35 T 16 R 122  
 BOOK PAGE 56 LINE 28

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Korkish #1, Sec. 35-16-12, Barton County, Kansas, as reflected by filed of the Mallard Drilling Company.

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this \_\_\_\_\_ day of November 1952.

My commission expires \_\_\_\_\_

NOTARY PUBLIC  
 No. 7142  
 TOLSON DIVISION  
 Kansas