

15-009-22889-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

Form CP-4
12-15-80
RECEIVED
STATE CORPORATION COMMISSION
DEC 08 1982
12-8-82
CONSERVATION DIVISION
Wichita Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 36 TWP. 16S RGE. 12 E/W
Location as in quarters or footage from lines:
NW SE NW

Lease Owner White & Ellis Drilling, Inc.
Lease Name Seyfert Well No. #1
Office Address 401 E. Douglas - Suite 500 Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 11-21-82
Application for plugging filed 11-21-82
Plugging commenced 11-21-82
Plugging completed 11-21-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin

Producing formation _____ Depth to top _____ bottom _____ T.D. 3399'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	405'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Mud to 3380', Spot 20 sx. cement thru drill pipe.
- Mud to 810', Spot 100 sx. cement thru drill pipe.
- Mud to 240', Spot 40 sx. cement thru drill pipe.
- Mud to 40', Spot 10 sx. cement thru drill pipe.
- Spot 10 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.


Ernest Sifford (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Ernest Sifford
401 E. Douglas #500 Wichita,
(Address) Ks. 67202

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1982

Carolyn J. Tjaden
Carolyn J. Tjaden - Notary Public.

My Commission expires:





15-009-22889-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: White & Ellis Drilling, Inc. 401 E. Douglas - Suite 500 Wichita, Kansas 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Seyfert Well No. #1

Sec. 36 T. 16S R. 12W Spot NW SE NW

County Barton State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 405' with 225 sx. 2% gel
3% cc

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 3399'

Drilling Commenced 11-15-82 Drilling Completed 11-21-82

Formation	From	To	Tops
Cellar	0	7	
Shale	7	1238	
Shale, Lime	1238	2610	
Shale	2610	2667	
Lime	2667	3399	

RECEIVED
STATE CORPORATION COMMISSION
DEC 08 1982
CONSERVATION DIVISION
Wichita Kansas