

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barton County, Sec. 36 Twp. 16 Rge. (E) 12(W)

Location as "NE/CNW&SW" or footage from lines NW SW NE

Lease Owner Thunderbird Drilling, Inc.

Lease Name Seyfert Well No. 1

Office Address 1311 Union National Bank Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 5, 1956 19

Application for plugging filed May 11, 1956 19

Application for plugging approved May 11, 1956 19

Plugging commenced May 11, 1956 19

Plugging completed May 14, 1956 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundage

Producing formation Arbuckle Depth to top 3374 Bottom 3391 Total Depth of Well 3391 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	279	8 5/8"	279'	0
		0	3375	5 1/2"	3375'	3075'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 3391 to 3365 - dumped 5 sacks cement mudded hole to 310' - set 10' rock bridge - dumped 20 sacks cement - mudded to 35' - set rock bridge - dumped 10 sacks cement.

Name of Plugging Contractor R & D Casing Pulling Company License # 236  
Address P. O. Box 569 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Charles W. Aikins, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Aikins, Jr.  
1311 Union National Bank Bldg.  
Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 11th day of June, 1956

My commission expires August 25, 1956

Leta Helm Notary Public

PLUGGING  
FILE SEC 36 T 16 R 12W  
BOOK PAGE 62 LINE 2

RECEIVED  
JUN 12 1956  
WICHITA, KANSAS

15-009-06309-00-00

SEYFERT #1

LOCATION: NW SW NE - Sec. 36,  
Twp. 16.S, Rge. 12.W,  
Stafford County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.  
1311 Union National Bank Bldg.  
Wichita, Kansas

SURFACE CASING: 8 5/8" set at 279' with 135  
sacks cement, 1% gel and 2 sacks  
Calcium Chloride.

OIL STRING: 5 1/2" set at 3375' with  
50 sacks cement, 2% gel.

ELEVATION: 1922' K. B.  
1919' D. F.  
1917' G. L.

COMMENCED: April 8, 1956

COMPLETED: April 18, 1956

WELL LOG

0	-	60	Soil and Rock
60	-	370	Shale and Shells
370	-	570	Sand and Shale
570	-	780	Red Bed
780	-	810	Anhydrite
810	-	1250	Shale and Shells
1250	-	1470	Broken Lime
1470	-	1650	Lime
1650	-	1870	Lime and Shale
1870	-	1945	Shale and Shells
1945	-	2159	Lime and Shale
2159	-	2585	Shale and Shells
2585	-	2650	Lime and Shale
2650	-	3020	Lime
3020	-	3052	Lime and Shale
3052	-	3082	Shale
3082	-	3270	Lime
3270	-	3380	Lime and Shale
3380	-	3391	Lime
3391			Rotary Total Depth

The undersigned, Charles W. Aikins, Jr., an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1 Seyfert as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.

  
Charles W. Aikins, Jr., Pres.

Subscribed and sworn to before me this 24th day of April, 1956.

  
Leta Helm - Notary Public

My commission expires:  
August 25, 1956

FILE SEC 36 Twp. 16. S. R. 12. W.  
BOOK PAGE 67 LINE 2

RECEIVED  
STATE CORPORATION COMMISSION  
APR 25 1956  
CONSERVATION DIVISION  
Wichita, Kansas