

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

T 16S NORTH R 12W

			*
	36		

Locate well correctly on above  
Section Plat

Barton County, Sec. 36 Twp. 16S Rge. 12W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW NE NE  
Lease Owner West Supply Co., Inc.  
Lease Name Hoffman Well No. 1  
Office Address Box 506 - Chase, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 27 19 55  
Application for plugging filed June 7 19 56  
Application for plugging approved June 8 19 56  
Plugging commenced June 8 19 56  
Plugging completed June 12 19 56  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Brundage  
Producing formation Depth to top Bottom Total Depth of Well 3350 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	240'	None
				5-1/2"	3080'	2695'
				Hole was plugged back to 3020'. Pipe perforated from 3012' to 3016'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled the hole with sand from 3020' to 3000'  
and ran 5 sacks of cement. Cement filled to 2960'.  
Mudded the hole to 230', set a 10' rock bridge  
and ran 20 sacks of cement. Mudded the hole to  
35', set a rock bridge and ran 10 sacks of cement  
on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Noel J. Knight (XXXXXX) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Hoff Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th. day of June 19 56

My commission expires May 20, 1957

Notary Public.

PLUGGING  
FILE SEC. 36 T. 16 R. 12W  
BOOK PAGE 69 LINE 20

JUL 13 1956  
6-13-56  
WICHITA, KANSAS

15-009-06308-00-00

Well Log  
Hoffman #1

NW NE NE/4 36-16-12  
Barton County, Kansas

85-240-CC 175 ft

0 - 85	Surface clay and post rock
85 - 135	Sand and gravel
135 - 320	Shale and shells
320 - 410	Sand
410 - 460	Shale and shells
460 - 625	Shale and red bed
625 - 640	Sand
640 - 758	Red bed
758 - 785	Anhydrite
785 - 1445	Shale and shells
1445 - 1490	Sand
1490 - 1565	Shale and shells
1565 - 1625	Sand
1625 - 1790	Shale and shells
1790 - 1835	Sandy lime and shale
1835 - 1925	Lime and shale
1925 - 2115	Lime and sandy shale
2115 - 2265	Lime and shale
2265 - 2425	Shale and lime
2425 - 2620	Shale and shells
2620 - 2675	Shale and lime
2675 - 2868	Lime and shale
2868 - 2967	Lime
2967 - 2969	Shale (Heebner)
2969 - 3017	Lime
3017 - 3060	Sand and shale
3060 - 3290	Lime
3290 - 3350	Lime and shale
3350	T. D.

STATE OF KANSAS  
COUNTY OF BARTON

A. L. Jackson, owner of A. L. Jackson Drilling Company, being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

A. L. Jackson  
A. L. Jackson

Subscribed and sworn before me this 27th day of December, 1955

Virgil E. Beilford, Jr.  
Virgil E. Beilford, Jr.  
Notary Public Barton County

My commission expires April 27, 1957.

RECEIVED  
OIL CORPORATION COMMISSION  
JUN 8 1956  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 36 T. 16 R. 12W  
BOOK PAGE 69 LINE 20