

BROOKS PIERCE DRILLING COMPANY
 UNION NATIONAL BANK BUILDING
 WICHITA 2, KANSAS

WELL NO. 1
 NE NE SW of Section 36-16S-12W
 Barton County, Kansas

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay & Rock	0	125	8-5/8" Surface Pipe @ 300', cemented with 200 sacks of cement and 100-lbs. calcium chloride.
Blue and Red Shale	125	195	
Sand	195	280	
Shale & Shells	280	300	
Shale & Shells	300	375	
Blue Shale & Sand	375	425	
Shale, Shells & Sand	425	545	
Shale & Shells	545	610	
Red Bed & Shale	610	775	
Anhydrite	775	800	
Shale	800	1010	
Shale & Shells	1010	1195	
Salt & Shale	1195	1305	
Shale & Shells	1305	1450	
Lime	1450	1965	
Shale & Lime	1965	2090	
Lime	2090	2150	
Shale & Shells	2150	2540	
Shale, Shells & Lime	2540	2720	
Gray Lime	2720	2750	
Lime	2750	2974	
Shale	2974	2978	
Lime	2978	3000	
Shale & Sand	3000	3078	
Lime	3078	3340	
Conglomerate	3340	3351	
Arbuckle	3351	3375	
Lime	3375	3401	
Total Depth:		3401'	Plugged.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify the foregoing to be a true and accurate
 Driller's Log of the formations encountered in the above well. MAR - 3 1951

CONSERVATION DIVISION

BROOKS PIERCE DRILLING COMPANY Wichita, Kansas

PLUGGING
 FILE SEC T R
 PAGE OF

By: Brooks Pierce
 Brooks Pierce, Owner

Subscribed and sworn to before me this 28th day of February, 1951.

Louise A. Bowman

My Commission expires September 8, 1954. Notary Public