

15-009-00138-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 36 Twp. 16 Rge. 12 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SW NE SW

Lease Owner Duke & Wood Drilling Co.

Lease Name Riemann Well No. 1

Office Address Box 194, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed November 14, 1952

Application for plugging filed November 14, 1952

Application for plugging approved November 14, 1952


Plugging commenced November 14, 1952

Plugging completed November 14, 1952

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3374 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	294'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 290', set bottom plug, dumped 20 sacks of cement wet thru drill pipe. Filled with heavy mud to 35', set plug, dumped 10 sacks of cement, filled to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1952
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke & Wood Drilling Company
Address Box 194, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Cecil M. Olson (employee of owner) ~~representative~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M Olson
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 1952
Dean T. Dooley
Notary Public.

My commission expires April 29, 1953.

PLUGGING
FILE SEC 36716 D 122
BOOK PAGE 60 LINE 27

15-009-00138-00-00

WELL LOG
Riemann #1
SW NE SW 36-16-12W
Barton County, Kansas

Started November 3, 1952
Completed November 14, 1952

Elevation 1897 KB
Heebner 2978 (-1081)
Lansing 3094 (-1197)
Conglomerate 3349 (-1452)

0-40	Surface clay
40-105	Post rock, sand and shale
105-280	Sand, shale and clay
280-294	Shale and clay
294-465	Shale, clay and iron
465-520	Dry sand and iron
520-762	Red bed
762-789	Anhydrite
789-1660	Shale and shells
1660-1935	Lime and shale
1935-2360	Lime and shale
2360-2770	Lime and shale
2770-2875	Lime
2875-2995	Lime
2995-3140	Lime
3140-3218	Lime
3218-3349	Lime
3349-3374	Conglomerate
3374	TOTAL ROTARY DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton .SS

I, FRANK G. WOOD, of the DUKE & WOOD DRILLING COMPANY
~~Lynn O. Duke~~
being first duly sworn on oath, state; That I have knowledge of the
facts, statements and matters herein contained and that the same are
true and correct.

Frank G. Wood
Partner

Subscribed and sworn to before me this 24th day of November 1952.

R. Dean Cooley
Notary Public
STATE CORPORATION COMMISSION

My commission expires: April 29, 1953.

NOV 25 1952

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 36-16-12W
HOOK PAGE 60 LINE 27