

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record

K.A.R. -82-3-117

RECEIVED

SEP 16 2002

KCC WICHITA

API NUMBER 15-185-23165-0000
LEASE NAME Asher
WELL NUMBER #1-3

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1320 Ft. from South Line of Section
610 Ft. from West Line of Section

LEASE OPERATOR F.G. Holl Company, L.L.C. SPOT LOCATION 50' W. of W/2 Sw
ADDRESS P.O. Box 780167 Section 3 Township 21s Range 14w
CITY, STATE, ZIP Wichita, Kansas 67278-0167 County Stafford
PHONE # 316-684-8481 Date Well Completed Sept.12, 2002
Character of Well Dry and Abandoned Date Plugging Commenced Sept.12, 2002
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed Sept.12, 2002

The plugging proposal was approved on September 10, 2002 (date)
by Scott Alberg (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3710

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	180			
Redbeds	Shale	180	830			
Anhydrite		830	853			
Shales		853	881	8-5/8"	870'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Received plugging orders from Scott Alberg on 09/10/02. Plugged on 09/12/02 in the following manner, using 145 sx 60/40 Poz, 6% Gel with heavy mud in hole and between all plugs; 1st plug at 3637' with 40sx, 2nd plug at 850' with 50sx, 3rd plug at 250' with 30sx, 4th plug at 40' cemented to surface. Rathole-15 sx. No mousehole. Plug down at 2:30 am on 09/12/02. Acid Services #5289.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 13th day of September 2002



Pamela S. Fields
(Notary Public)

My Commission Expires: _____

OR

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Asher #1-3

LOCATION: 50' W. of W/2 Sw Section 3 T 21s R 14w
API: 15-185-23165-0000 Stafford County, Kansas

OWNER: F.G. Holl Company, L.L.C.
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 03-Sep-02
COMPLETED: 12-Sep-02

TOTAL DEPTH: **DRILLER** 3710 FEET
LOGGER 3712 FEET

Ground Elevation: 1933
KB Elevation: 1942

LOG

0 -	3 FEET	Top Soil
3 -	21 FEET	Clay
21 -	60 FEET	Fine Sand
60 -	85 FEET	Sand and Gravel
85 -	190 FEET	Sand, Gravel and Clays
190 -	830 FEET	Redbeds
830 -	853 FEET	Anhydrite
853 -	1810 FEET	Shales and Salt
1810 -	3636 FEET	Limestone, Shale and Dolomite
3686 -	3710 FEET	Arbuckle

RECEIVED
SEP 16 2002
KCC WICHITA

CASING RECORDS

Surface Casing-8-5/8"

Spud at 2:15 pm on 09/03/02. Drilled 12-1/4" hole to 881'. Ran 21 joints of new 23# 8-5/8" surface casing, tally 870' set at 881' KB. Cemented with 210 sx A-Con; 3% CC, 1/4# Celloflake, and 125sx common; 2% Gel, 3% CC and 1/4# Celloflake. Cement did circulate.
Plug down at 4:30 am on 09/04/02 by Acid Services. Ticket #5229. Strapped bottom 3 joints, welded collars remaining 18 joints.

Plugging Data

Received plugging orders from Scott Alberg on 09/10/02. Plugged on 09/12/02 in the following manner, using 145 sx 60/40 Poz, 6% Gel with heavy mud in hole and between all plugs; 1st plug at 3637' with 40sx, 2nd plug at 850' with 50sx, 3rd plug at 250' with 30sx, 4th plug at 40' cemented to surface. Rathole-15 sx. No mousehole. Plug down at 2:30 am on 09/12/02. Acid Services #5289.

DEVIATION SURVEYS

1	degree(s) at	881	feet
1	degree(s) at	3510	feet
1	degree(s) at	3641	feet
3/4	degree(s) at	3710	feet