

REC'D APR 28 1966

15.185.01852.0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 3 Twp. 21 Rge. 14 (E) W (W)
Location as "NE/CNW&SW¼" or footage from lines NW NW NW

Lease Owner W. H. Peachee

Lease Name Davis Well No. 3

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 4-23-66 19

Plugging completed 4-26-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 3549 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	806'	None
				5-1/2"	3549'	2779'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 3360' and dumped 5 sacks of cement @ 3360' with dump bailer. Pulled 5 1/2" casing, set rock bridge @ 300' and dumped 25 sacks of cement. Mudded hole to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (OWNER/OPERATOR) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of April, 1966

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

BARNETT DRILLING, INC.
LOG OF DAVIS WELL NO. 3
330' FWL AND 100' FWL, NW¼ SECTION 3-21S-11W,
STAFFORD COUNTY, KANSAS.

Commenced 10-25-55

Completed 11-9-55

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	-0-	195	
Shale and Shells	195	305	
Shale	305	385	
Sand	385	460	
Shale	460	803	
Anhydrite	803	806	Set 8-5/8" Surface Casing at 806 Feet; Cemented with 400 sacks.
Shale	806	1355	
Shale and Shells	1355	1790	
Shale	1790	1875	
Lime	1875	1955	
Shale and Lime	1955	2805	
Lime	2805	3010	
Shale and Lime	3010	3055	
Lime	3055	3523	
Shale and Lime	3523	3547	
Lime	3547	3549	
Total Depth		3549	Set 5 1/2" Casing; Cemented with 125 sacks.

RECEIVED
 STATE CORPORATION COMMISSION

APR 5 1966

CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATE

I, F. R. Stubblefield of Barnett Drilling, Inc. certify that to the best of my knowledge and belief, that the foregoing is a true and correct log of the Davis Well No. 3 located 330' FWL and 100' FWL in the NW¼ of Section 3-21S-11W, Stafford County, Kansas.

F. R. Stubblefield

Subscribed and sworn to by and before me in and for the County of Sedgwick, State of Kansas, this 29th day of November, 1955.

Mildred F. Willis

My commission expires February 27, 1956.