

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitling Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 3 Twp. 21 Rge. (E) 14 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SE NE
Lease Owner Westgate-Greenland Oil Company
Lease Name Martha Davis "A" Well No. 1
Office Address 1009 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed January 8, 1952 19
Application for plugging filed (orally) January 8, 1952 19
Application for plugging approved " January 8, 1952 19
Plugging commenced January 8, 1952 19
Plugging completed January 8, 1952 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	215	8 5/8"	215	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Filled hole with heavy mud from 3693 to 210 feet
Set plug at 210 feet and ran 15 sacks cement to 170 feet
Filled with heavy mud from 170 feet to 35 feet
Set plug at 35 feet and ran 10 sacks cement to cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1952
1-12-1952

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company
Address 1009 Central Building Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) or (owner of operation) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) G. E. Bitler
1009 Central Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11th day of January, 19 52
Esther Russell Notary Public.

PLUGGING
FILE SEC 3 T 21 R 140
BOOK PAGE 136 LINE 46

DRILLERS LOG

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: Jackson Drilling Corporation
 FARM: Martha Davis "A" 1
 LOCATION: NW SE NE Section 3-21S-14W,
 Stafford County, Kansas
 COMMENCED: December 27, 1951
 COMPLETED: January 8, 1952
 ELEVATION: 1917 DF

0	to	130	Sand
130	to	215	Sand and shale
215	to	255	Shale
255	to	330	Sand
330	to	810	Red Bed W/sand streaks
810	to	835	Anhydrite
835	to	1145	Shale and shells
1145	to	1260	Shale and shells W/salt
1260	to	1370	Shale and lime
1370	to	1585	Shale and shells
1585	to	1680	Shale and lime
1680	to	1790	Lime W/shale breaks
1790	to	1885	Lime and shale
1885	to	1990	Lime
1990	to	2170	Lime W/shale breaks
2170	to	3075	Lime and shale
3075	to	3125	Lime W/shale breaks
3125	to	3285	Lime and shale
3285	to	3318	Shale
3318	to	3329	Brown lime
3329	to	3526	Lansing lime
3526	to	3588	Lime, shale and chert
3588	to	3595	Lime and chert
3595	to	3628	Shale
3628	to	3658	Simpson Shale
3658	to	3693	Arbuckle lime
		3693	T. D. (RB)

set 215 feet of 8 5/8" surface pipe. Cemented with 150 sacks cement and 2 sacks calcium chloride.

Drill Stem Tests: 3451-74, open 3/4 hour, 7 min blow, recovered 8 foot mud, no BHP.
 3481-96, open 1 hour, 5 min blow, recovered 5 foot mud, no BHP.
 3609-26, open 3/4 hour, recovered 5 foot mud, no BHP.

TOPS: Heebner 3204. Brown Lime 3316. Lansing 3326. Base KC 3552.
 Viola 3561. Simpson 3592 Arbuckle 3656 (DF)

Ran Schlumberger
 Dry, plugged and abandoned

C E R T I F I C A T E

I, Don Allen, do hereby certify that the above and foregoing is a true and correct copy of log of the Martha Davis "A" 1, Section 3-21-14W, Stafford County, Kansas, as reflected by files of the Westgate-Greenland Oil Company.

Don Allen
 Don Allen

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 11th day of January, 1952.

My commission expires May 25, 1953.

Ether Russell
 Notary Public

PLUGGING

FILE SEC-3-21-14W
 BOOK PAGE 136 LINE 44