


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
245 North Water  
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County, Sec. 3 Twp. 21 Rge. 14 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW NE NE  
Lease Owner Jay C. Boyer  
Lease Name Davis #2 Well No.  
Office Address Hays, Kansas 67601  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 3/22/76 19  
Plugging completed 3/26/76 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 3665 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	FEET IN	PULLED OUT
				8-5/8	421	none
				4 1/2"	3604	2317'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3300' and dumped 4 sacks cement.  
Shot pipe at 3135', 3042', 2934', 2824', 2732', 2636', 2511', 2409', 2311', pulled 73 joints of 4 1/2" casing. Allied pumped 2 sacks hulls, 10 sacks gel and 100 sacks cement.

PLUGGING COMPLETE. MARCH 26 1976  
CONSERVATION DIVISION  
WICHITA, KANSAS

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC. 5-4-1976  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 31st day of March 1976

My commission expires MARGARET MELCHER  
Notary Public  
Rice County, Ks.  
My Comm. Exp. Feb. 15, 1979

## DRILLERS LOG

Lease Name            Davis No. 1  
 Location-            SW <sup>NE</sup> SW NE<sub>4</sub> Sec. 3-21-14W.    Stafford County, Kansas.  
 Contractor:-        Adkins Drilling Company, Inc.

Formation	From	To	Formation	From	To
Surface Hole	0	212			

Set 8 5/8" @ 207' cemented  
 with 150 Sacks of Cement  
 and 200lbs Calcium Chloride.

Plug	182	183
Cement	183	209
Open Hole	209	212
Sand, Shale & Redbed	212	600
Shale, sand & Red Bed	600	810
Anhydrite	810	841
Red bed and shale	841	1100
Red Bed, Shale & Shells	1100	1700
Shale, Shells & Lime	1700	1860
Shale & Lime	1860	2165
Lime & Shale	2165	2232
Shale & Lime	2232	2565
Shale	2565	2820
Shale & Lime	2820	3180
Lime	3180	3235
Lime & Shale	3235	3310
Lime	3310	3585
Conglomerite	3585	3628
Dolomite	3628	3635'

T. D. 3635'  
 Set 5 1/2" Casing @ 3629' cemented with 150  
 Sacks of cement.

I hereby certify that the foregoing is true and correct to the  
 best of my knowledge and belief.

Adkins Drilling Company, Inc.

By *Pauline B. Adkins*

Secy-Treas.

*Plugging #49*

PLUGGING	
FILE	SEC 3 T 21 R 14W
BOOK	PAGE 28 LINE 24

RECEIVED  
 STATE CONSERVATION COMMISSION

JUL 17 1957

CONSERVATION DIVISION  
 Wichita, Kansas